



NOTE:  
 REPLACE SIGNS IN MEDIANS,  
 CONSTRUCT 12"x12" BLOCKOUTS  
 FOR EACH SIGN

LOCATION	STANDARD NUMBER	HEIGHT	DISTANCE FROM CENTER LINE
F. A. P. ROUTE IL 17		FOOT	FOOT
STA. 37+75 RT.	W12-1	7'	57'
STA. 37+83 RT.	R5-1	7'	55'
STA. 37+85 RT.	R5-1A	7'	55'
STA. 37+83 LT.	R4-7	7'	2'
STA. 37+85 LT.	R1-1	7'	41'
STA. 38+60 LT.	R6-1	7'	1'
STA. 39+51 LT.	R1-1	7'	33'
STA. 39+56 LT.	R4-7	7'	2'
STA. 39+83 LT.	R1-1	7'	43'
STA. 39+79 LT.	R4-7	7'	128.5'
STA. 39+83 LT.	R6-1	7'	52'
STA. 39+83 LT.	R5-1A	7'	91'
STA. 41+69 RT.	R4-7	7'	2'

FILE NAME =  
 c:\projects\ed83288\details.dgn

USER NAME = corcoranlm	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 50,0000' / IN.	CHECKED -	REVISED -
PLOT DATE = Mar 25, 2008 - 01:34:36 PM	DATE -	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**DETAILS**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 41	SECTION (152)1	COUNTY LIVINGSTON	TOTAL SHEETS 10	SHEET NO. 6
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 66764	