

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% ST.
CODE NO.	CONSTRUCTION CODE TYPE: ITEM	UNIT	I000
			TOTAL QUANTITY
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	21380
40600300	AGGREGATE (PRIME COAT)	TON	535
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	40
40600535	LEVELING BINDER (HAND METHOD), N70	TON	134
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	7483
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600990	TEMPORARY RAMP	SQ YD	2154
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	11225
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	133625
48101200	AGGREGATE SHOULDERS, TYPE B	TON	452
56109210	WATER VALVES TO BE ADJUSTED	EACH	5
60255500	MANHOLES TO BE ADJUSTED	EACH	3
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	3
60403800	LIDS, TYPE 1, CLOSED LID	EACH	6
66700095	PERMANENT SURVEY MARKERS	EACH	2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1

SUMMARY OF QUANTITIES (CONTINUED)			URBAN 80% FED. 20% ST.
CODE NO.	CONSTRUCTION CODE TYPE: ITEM	UNIT	I000
			TOTAL QUANTITY
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10123
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	5411
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	190752
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	34434
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	14895
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2007
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	2115
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1125
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1804
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	63584
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2314
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	4965
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	669
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	705
78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	9164
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	904
78200300	PRISMATIC CURB REFLECTOR	EACH	53
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	904
88600100	DETECTOR LOOP, TYPE I	FOOT	4698
X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1
X8860100	LOOP DETECTOR TESTING	EACH	5
Z0024430	FLAGGER	HOURL	100
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1
Z0076600	TRAINEES	HOURL	1000

† Y080
• SPECIALTY ITEMS

FILE NAME =	USER NAME = aarpenterdj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
o:\projects\43668805\43668805 - sht-soq.dwg		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	623/790	(30,30X-1,2)RS-3&E)RS-1	LASALLE	24	3
		CHECKED -	REVISED -												
		DATE -	REVISED -												
		PLOT SCALE = 1/8" = 1' / IN.													
		PLOT DATE = Mar 21, 2009 - 02:35:51 PM													
											CONTRACT NO. 66805				
											FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				