

SUMMARY OF QUANTITIES

LOCATION OF WORK:

FAI - 74
VERMILION COUNTY

Sta. 1880+00.00 to 1955+00.00

Urban Multilane
100% STATE
J000-2A

CONSTRUCTION TYPE CODE:

<u>CODE NO.</u>	<u>ITEM</u>	<u>UNIT</u>	<u>TOTAL QUANTITY</u>
42001200	PAVEMENT FABRIC	SQ YD	65.0
44201007	CLASS B PATCHES, TYPE II, 13 INCH	SQ YD	400.0
44201011	CLASS B PATCHES, TYPE III, 13 INCH	SQ YD	32.0
44201013	CLASS B PATCHES, TYPE IV, 13 INCH	SQ YD	35.0
44213200	SAW CUTS	FOOT	2,500.0
67100100	MOBILIZATION	L SUM	1.0
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	8.0
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1.0
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	11.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	440.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28.0
Z0017100	DOWEL BARS	EACH	1,000.0
Z0075300	TIE BARS	EACH	13.0

* SPECIALTY ITEMS

FILE NAME = c:\projects\4570705\70705plans.dgn	USER NAME = collierbw	DESIGNED - RTB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE. 74	SECTION (92-111)	COUNTY VERMILION	TOTAL SHEETS 17	SHEET NO. 4
PLOT SCALE = 100.0000' / IN.	CHECKED -	DRAWN - JRP	REVISED -	SCALE: NA	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	CONTRACT NO. 70705		
PLOT DATE = 3/13/2008	DATE - 12-07	REVISED -	REVISED -	FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT						