					NHS 80% FEDERAL 20% STATE	STP 80% FEDERAL 20% STATE	NHS 80% FEDERAL 20% STATE	NHS 80% FEDERAL 10% STATE 10% CITY	NHS 80% FEDERAL 13.33% STATE 6.67% CITY	STP 80% FEDERAL 10% STATE 10% CITY	STP 80% FEDERAL 13.33% STATE 6.67% CITY	STP 80% FEDERAL 10% STATE 10% COUNTY	NHS 80% FEDERAL 10% STATE 5% CITY 5% SOUTHERN VIEW	NHS 80% FEDERAL 10% STATE 10% CITY
	LOCATION OF WORK			URBAN	ROADWAY NORTH OF I-72 SEE NOTE 1	ROADWAY SOUTH OF I-72	SW PLAZA DR.	SIGNALS NORTH OF I-72 SEE NOTE 2	SIGNALS NORTH OF I-72 SW PLAZA DR.	SIGNALS SOUTH OF I-72 REC. DR. MATHERS RD	SIGNALS SOUTH OF I-72 PANTHER CR. DR.	SIGNALS SOUTH OF I-72 WOODSIDE RD.	SIGNALS 6TH ST @ LINTON	SIGNALS 6TH ST. @ APPLE ORCHARD
	SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE									
	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	I000	I000	I000-1A	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F
*	X0320872	VIDEO VEHICLE DETECTION SYSTEM	EACH	7				3	1	1	1	1		
	X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	292			292							
	X0322929	CAMERA MOUNTING ASSEMBLY	EACH	8				6			2			
*	X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6 1C (GREEN)	FOOT	2,948				1,208	677				566	497
	X0325281	CULVERT REPAIR	EACH	1		1								
	X0484300	MEDIAN INLET BOX REMOVAL	EACH	1			1							
*	X2020500	EARTH EXCAVATION (ROCKFILL)	CU YD	2,251			2,251							
	X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	99	55	44								
	X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	5,626	2,818	2,808								
	X6064201	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.06	FOOT	2,234	1,600	634								
	X6065701	CONCRETE MEDIAN, TYPE SM-4.06	SQ FT	1,221	1,221									
*	X7800620	URETHANE PAVEMENT MARKING - LINE 5"	FOOT	119,466	60,668	56,486	2,312							
*	X7800640	URETHANE PAVEMENT MARKING - LINE 8"	FOOT	13,701	7,687	4,804	1,210							
*	X7800650	URETHANE PAVEMENT MARKING - LINE 12"	FOOT	6,266	3,482	1,993	791							
*	X8170245	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 12	FOOT	961					961					
*	X8804030	SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 1-3 SECTION, 1-4 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	4				2					1	1
*	X8950200	REBUILD EXISTING HANDHOLE	EACH	7				6		1				
	XX004096	REMOVE AND RE-INSTALL CONCRETE FLARED END SECTIONS	EACH	1		1								
	XX004350	TRANSVERSE DRAINS COMPLETE	EACH	5			5							
	Z0017100	DOWEL BARS	EACH	276	276									
	Z0033600	LONGITUDINAL JOINT REPAIR	FOOT	11,193	5,773	5,420								
	Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	1,602			1,602							
*	Z0054530	ROCKFILL -SUBGRADE	TON	2,048			2,048							
	Z0075300	TIE BARS	EACH	5,840	4,004	1,836								
	X0325989	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-4.24	FOOT	77	77									
	X0325990	REMOVE LIGHTED PAVEMENT MARKERS	EACH	99	99									
*	X0325991	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 18 3/C	FOOT	4,694				2,362	961	192	987	192		

*SPECIALTY ITEMS

CUMMINS ENGINEERING CORPORATION

JOB - 2200
FILE - sht-S00.dgn

FILE NAME = C:\Projects\d652204\cummins_final\d672889-sht-s00.dgn
USER NAME = laughlinrl
PLOT SCALE = 100.0000 ' / IN.
PLOT DATE = Mar-20-2008 07:16:12AM

DESIGNED - NAK
DRAWN - AJH
CHECKED - NAK
DATE - 3/15/2008

REVISED - NAK (3/19/2008)
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	2-2(RS) & 3-1, 2(RS-10, TS-5)	SANGAMON	181	11
		CONTRACT NO. 72889		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		