

PATCHING SCHEDULE

APPROX. STA	LOCATION	LENGTH (FT)	WIDTH (FT)	CL A PATCHES TY II, 8" (SQ YD)	CL A PATCHES TY III, 8" (SQ YD)	CL A PATCHES TY IV, 8" (SQ YD)	TIE BARS (EACH)	PATCHING REINFORCEMENT (SQ YD)	SAW CUTS (FT)
36+50	SBDL	8	12	10.67				10.67	64
48+30	SBDL	5	12	6.67				6.67	58
48+40	SBDL	5	12	6.67				6.67	58
48+70	SBDL	5	12	6.67				6.67	58
48+80	SBDL	5	12	6.67				6.67	58
50+50	SBDL	5	12	6.67				6.67	58
70+20	SBDL	5	12	6.67				6.67	58
70+50	SBDL	5	12	6.67				6.67	58
73+00	SBDL	5	12	6.67				6.67	58
74+00	SBDL	5	12	6.67				6.67	58
74+30	SBDL	5	12	6.67				6.67	58
76+50	SBDL	5	12	6.67				6.67	58
80+20	SBDL	5	12	6.67				6.67	58
80+50	SBDL	16	12		21.33			21.33	80
83+00	SBDL	5	12	6.67				6.67	58
91+00	SBDL	8	12	10.67				10.67	64
91+30	SBDL	5	12	6.67				6.67	58
94+00	SBDL	5	12	6.67				6.67	58
97+10	SBDL	5	12	6.67				6.67	58
113+80	SBDL	5	12	6.67				6.67	58
132+60	SBDL	8	12	10.67				10.67	64
133+10	SBDL	16	12		21.33			21.33	80
133+70	SBDL	5	12	6.67				6.67	58
134+70	SBDL	26	12			34.67	13	34.67	100
137+50	SBDL	5	12	6.67				6.67	58
197+90	SBDL	5	12	6.67				6.67	58
141+00	SBDL	10	12	13.33				13.33	68
146+70	SBDL	15	12		20.00			20.00	78
147+20	SBDL	10	12	13.33				13.33	68
148+20	SBDL	62	12			82.67	31	82.67	172
148+80	SBDL	16	12		21.33			21.33	80
155+50	SBDL	5	12	6.67				6.67	58
158+95	SBDL	6	12	8.00				8.00	60
159+05	SBDL	5	12	6.67				6.67	58
162+70	SBDL	30	12			40.00	15	40.00	108
163+00	SBDL	5	12	6.67				6.67	58
164+00	SBDL	5	12	6.67				6.67	58
165+50	SBDL	8	12	10.67				10.67	64
STA. EQU.	285+95.95bk+00+00ah								
2+10	SBDL	12	12		16.00			16.00	72
25+80	SBDL	8	12	10.67				10.67	64
69+50	SBDL	0	12	13.33				13.33	68
117+20	SBDL	8	12	10.67				10.67	64
121+30	SBDL	12	12		16.00			16.00	72
122+00	SBDL	5	12	6.67				6.67	58
131+80	SBDL	5	12	6.67				6.67	58
132+30	SBDL	8	12	10.67				10.67	64
134+40	SBDL	5	12	6.67				6.67	58
135+80	SBDL	8	12	10.67				10.67	64
139+80	SBDL	5	12	6.67				6.67	58
140+50	SBDL	5	12	6.67				6.67	58
STA. EQU.	197+82.00bk+30+87.58ah								
33+80	SBDL	8	12	10.67				10.67	64
35+20	SBDL	5	12	6.67				6.67	58
37+50	SBDL	5	12	6.67				6.67	58
43+10	SBDL	5	12	6.67				6.67	58
TOTAL: SOUTHBOUND LANES				357.33	116.00	157.33	59	630.67	3,538
80+00	NBDL	5	12	6.67				6.67	58
80+70	NBDL	5	12	6.67				6.67	58
92+30	NBDL	8	12	10.67				10.67	64
92+50	NBDL	5	12	6.67				6.67	58
106+20	NBDL	5	12	6.67				6.67	58
106+30	NBDL	5	12	6.67				6.67	58
109+00	NBDL	12	12		16.00			16.00	72
110+40	NBDL	14	12		18.67			18.87	76

NOTE:

* AN ADDITIONAL 10% OF THE ESTIMATED PATCHING QUANTITIES WAS ADDED TO BE USED AT THE DISCRETION OF THE ENGINEER.

PATCHING SCHEDULE
FAI 172 (I-172)
SECTION D6 PATCHING 2009
ADAMS COUNTY