SUMMARY OF QUANTITIES (Cont'd)

	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODES: FAI 72 ROADWAY 4 LANE 90% FED 10% STATE	FAI 72 BRIDGE SN 058-0093 90% FED 10% STATE	FAI 72 BRIDGE SN 058-0094 90% FED 10% STATE	FAI 72 BRIDGE SN 058-0095 90% FED 10% STATE	FAI 72 BRIDGE SN 058-0096 90% FED 10% STATE	FAI 72 BRIDGE SN 058-0097 90% FED 10% STATE
					1000	X031-2A	X031-2A	X531-2A	X531-2A	X231-2A
	52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12		6	6			
	52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	44		6	6	12	12	8
	52100540	ANCHOR BOLTS, 1 1/2"	EACH	16						16
	60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	3	3					
	60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	42	42					
	60500310	FILLING INLETS, SPECIAL	EACH	8	8					
*	63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1350	1350					
*	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	6	6					
*	63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	7	7					
*	63100215	TRAFFIC BARRIER TERMINAL, TYPE 6 (SPECIAL)	EACH	3	3					
	63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	1368.5	1368.5					
	63500105	DELINEATORS	EACH	175	175					
	64200105	SHOULDER RUMBLE STRIP	FOOT	75717	75717					
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12					
	67100100	MOBILIZATION	L SUM	1	1					
	70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1	1					
	70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	3	3					
	70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4	4					
	70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1					
	70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1					
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15	15					
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	29208	29208					
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	3625	3625					
	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	3625	3625					
*	78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	84676	81483	836.5	836.5	760	760	
*	78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	10645	10246	104.5	104.5	95	95	
*	78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	1687	1687					
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1078	1078					
*	78100105	RAISED REFLECTIVE PAVEMENT MARKER BRIDGE)	EACH	40		10	10	10	10	
*	78200410	GUARDRAIL MARKERS, TYPE A	EACH	54	54					
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	7	7					
	X0320157	CLEANING UNDERDRAIN OUTLETS	EACH	122	122					
	X0321468	PLUG EXISTING DECK DRAINS	EACH	174		33	33	46	46	16
	X0322729	MATERIAL TRANSFER DEVICE	TON	22147	22147					
	X0323644	PAVEMENT MARKING GROOVING	FOOT	3725	132.8	941.1	941.1	855	855	
	X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	888		121	167	266	193	141
	X0349800	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	EACH	3	3					
	X4401705	PARTIAL DEPTH REMOVAL	SQ YD	848	848					
	X4421000	PARTIAL DEPTH PATCHING	TON	143	143					
	X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28	28					
	XZ193500	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"	SQ YD	6501		1740	1749	1506	1506	
	Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	7400		1740	1749	1506	1506	899
	Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	38		7	7	10	10	4
	Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	117		10	18	26	32	31
	Z0017100	DOWEL BARS	EACH	120	120					
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1				0.5	0.5	
	Z0075300	TIE BARS	EACH	42	42					
	52100520	ANCHOR BOLTS, 1"	EACH	96		24	24	24	24	
	X0325983	BRIDGE DECK FLY ASH OR GGBF SLAG CONCRETE OVERLAY, 2 1/4"	SQ YD	899						899
@	Z0076600	TRAINEES	HOUR	500	500					

@ YOBO
* SPECIALTY ITEMS

Rev.

FILE NAME = c:\projects\74171d\shtsoq_74171.dgn	USER NAME = swartzrw	DESIGNED - JLD	REVISED -
		DRAWN - RWS	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	CHECKED - WES	REVISED -
	PLOT DATE = 3/25/2008	DATE - 10-07	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES (2 OF 2)

SCALE: NA | SHEET NO. 2 OF 2 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	(58,74)(66,67)RS-1	MACON	88	5
		CONTRACT NO. 74171		

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT