

PAVING SCHEDULE
(RAMPS)

STATION		TO	STATION	LENGTH FEET	RAMP WIDTH FEET	AREA SQ. YD.	BITUMINOUS MATERIALS (PRIME COAT) GALLON	AGGREGATE (PRIME COAT) TON	POLYMERIZED HOT MIX ASPHALT SURFACE COURSE, MIX "D", N105 TON	POLYMERIZED HOT MIX ASPHALT BINDER COURSE, IL-19.0, N105 TON	HOT MIX ASPHALT SHOULDERS TON	HOT MIX ASPHALT SHOULDERS, 1 1/2" SQ. YD.	HOT MIX ASPHALT REMOVAL, 1" SQ. YD.	HOT MIX ASPHALT REMOVAL, 1 1/2" SQ. YD.	HOT MIX ASPHALT REMOVAL, 3 1/4" SQ. YD.	HOT MIX ASPHALT REMOVAL, VARIABLE DEPTH SQ. YD.	TEMPORARY RAMP SQ. YD.	AGGREGATE SHOULDERS, TYPE B TON	PAVEMENT REMOVAL SQ. YD.	
RAMP D																				
132+08.20	TO	140+38.58	830.4	16.0	3530.7	203.0	4.1	69.8	104.6	46.5	553.6				738.1				7.9	
126+13.69	TO	132+08.20	594.5	16.0	2811.2	158.5	3.2	88.8	133.2	44.4	528.5				1056.9				68.9	
124+93.80	TO	126+13.69	119.9	16.0	5394.7	34.6	0.7	17.9	26.9	11.2	133.2				213.1				11.2	
RAMP A																				
100+00.00	TO	103+22.00	322.0	16.0	1367.7	78.7	1.6	27.0	40.6	18.0	214.7				286.2				3.1	
103+22.00	TO	106+19.79	297.8	16.0	12381.6	79.4	1.6	44.5	66.7	22.2	264.7				529.4				30.3	
106+19.79	TO	107+62.40	142.6	16.0	3707.9	41.2	0.8	21.3	31.9	13.3	158.5				253.5				7.7	
RAMP C																				
106+26.18	TO	107+05.10	78.9	16.0	2231.1	22.8	0.5	11.8	17.7	7.4	87.7				140.3				4.6	
103+59.03	TO	106+26.18	267.2	16.0	12368.1	71.2	1.4	39.9	59.8	19.9	237.5				474.9				30.3	
100+00.00	TO	103+59.03	359.0	16.0	1370.4	87.8	1.8	30.2	45.2	20.1	239.4				319.1				3.1	
RAMP B																				
114+64.50	TO	115+44.60	80.1	16.0	2082.6	23.1	0.5	12.0	17.9	7.5	89.0				142.4				4.3	
115+44.60	TO	118+81.72	337.1	16.0	26054.6	89.9	1.8	50.3	75.5	25.2	299.7				374.6				63.8	
118+81.72	TO	129+10.60	1028.9	16.0	4360.8	251.5	5.0	86.4	129.6	57.6	685.9				914.6				9.8	
Median Cross Over Sta.	704+30				207.7	20.8		17.4			207.7									
Median Cross Over Sta.	708+56				207.7	20.8		17.4			207.7									
SHEET TOTALS				4,458		103,377	1,183	23	535	750	293		3,908		5,443				245	
PROJECT TOTALS				25,360		214,854	19,053	380	9,541	13,890	5,992	3,412	55,146	960	115,402	17,791	480		1,352	163