REVISED RESURFACING SCHEDULE

Location			Width	Length	HMA Surf. Rem. 2 1/2"	Bit. Mat'l (Pr Ct)	Agg (Pr Ct)	SMA 2 1/2"	MTD
STA	TO	STA	(FT)	(FT)	(SQ YD)	(TON)	(TON)	(TON)	(TON)
I 270 EASTBOUND									
120+64	TO	191+30	24	7066	18843	5.9	28.3	2638	2638
CHAIN OF ROCKS CANAL OMISSION									
211+21	TO	231+02	24	1981	5283	1.7	7.9	740	740
IL 3 OMISSION									
234+18	TO	255+32	24	2114	5637	1.8	8.5	789	789
ST. THOMAS RD. OMISSION									
258+30	TO	317+77	24	5947	15859	5.0	23.8	2220	2220
IL 203 OMISSION									
324+33	TO	334+21	24	988	2635	0.8	4.0	369	369
ENGINEERS RD OMISSION									
337+63	TO	399+94	24	6231	16616	5.2	24.9	2326	2326
IL 111 OMISSION									
402+77	TO	403+40	24	63	168	0.1	0.3	24	24
403+40	TO	405+60	30	220	733	0.2	1.1	103	103
405+60	TO	515+00	24	10940	29173	9.1	43.8	4084	4084
515+00	TO	515+81	36	81	324	0.1	0.5	45	45
COUNTY DITCH									
I 270 WESTBOUND									
120+64	TO	191+75	24	7111	18963	5.9	28.4	2655	2655
CHAIN OF ROCKS CANAL OMISSION									
211+63	TO	231+18	24	1955	5213	1.6	7.8	730	730
IL 3 OMISSION									
234+54	TO	255+33	24	2079	5544	1.7	8.3	776	776
ST. THOMAS RD. OMISSION									
258+40	TO	317+97	24	5957	15885	5.0	23.8	2224	2224
IL 203 OMISSION									
324+49	TO	334+02	24	953	2541	0.8	3.8	356	356
ENGINEERS RD OMISSION									
337+49	TO	400+03	24	6254	16677	5.2	25.0	2335	2335
IL 111 OMISSION									
402+96	TO	404+60	24	164	437	0.1	0.7	61	61
404+60	TO	408+00	26	340	982	0.3	1.5	138	138
408+00	TO	515+00	24	10700	28533	8.9	42.8	3995	3995
515+00	TO	515+81	36	81	324	0.1	0.5	45	45
COUNTY DITCH									
COLLECTOR / DISTRIBUTORS									
I 270 & IL 203 EASTBOUND									
296+40	TO	300+70	10	430	478	0.1	0.7	67	67
300+70	TO	317+77	15	1707	2845	0.9	4.3	398	398
324+33	TO	334+21	15	988	1647	0.5	2.5	231	231
337+63	TO	339+55	15	192	320	0.1	0.5	45	45
339+55	TO	346+76	10	721	801	0.3	1.2	112	112
I 270 & IL 203 WESTBOUND									
296+90	TO	304+30	10	740	822	0.3	1.2	115	115
304+30	TO	317+97	15	1367	2278	0.7	3.4	319	319
324+49	TO	334+02	15	953	1588	0.5	2.4	222	222
337+49	TO	344+00	15	651	1085	0.3	1.6	152	152
344+00	TO	348+35	10	435	483	0.2	0.7	68	68
I 270 & IL 255 EASTBOUND									
450+46	TO	482+08	15	3162	5270	1.6	7.9	738	738
SUB-TOTAL				82571	207989	65.1	312.0	29119	29119

REVISED RESURFACING SCHEDULE

Location			Width	Length	HMA Surf. Rem. 2 1/2"	Bit. Mat'l (Pr Ct)	Agg (Pr Ct)	SMA 2 1/2"	MTD
STA	TO	STA	(FT)	(FT)	(SQ YD)	(TON)	(TON)	(TON)	(TON)
IL 3 RAMPS									
RAMP A1									
+	TO	4+47	8	447	397	0.1	0.6	56	56
4+47	TO	5+73	19	126	266	0.1	0.4	37	37
5+73	TO	24+69	16	1896	3371	1.1	5.1	472	472
24+69	TO	25+57	25	88	244	0.1	0.4	34	34
25+57	TO	27+02	19	145	306	0.1	0.5	43	43
27+02	TO	29+08	18	206	412	0.1	0.6	58	58
29+08	TO	30+08	16	100	178	0.1	0.3	25	25
30+08	TO	31+20	13	112	162	0.1	0.2	23	23
31+20	TO	33+00	6	180	120	0.0	0.2	17	17
RAMP A2									
-1+10	TO	+	14	110	171	0.1	0.3	24	24
+	TO	1+00	16	100	178	0.1	0.3	25	25
1+00	TO	1+86	26	86	248	0.1	0.4	35	35
1+86	TO	16+52	16	1466	2606	0.8	3.9	365	365
16+52	TO	18+25	18	173	346	0.1	0.5	48	48
RAMP A3									
-2+20	TO	+	18	220	440	0.1	0.7	62	62
+	TO	1+70	24	170	453	0.1	0.7	63	63
1+70	TO	10+85	16	915	1627	0.5	2.4	228	228
10+85	TO	12+35	19	150	317	0.1	0.5	44	44
RAMP A4									
+	TO	5+70	15	570	950	0.3	1.4	133	133
5+70	TO	17+00	16	1130	2009	0.6	3.0	281	281
17+00	TO	22+00	10	500	556	0.2	0.8	78	78
RAMP A5									
+	TO	5+78	13	578	835	0.3	1.3	117	117
5+78	TO	20+78	16	1500	2667	0.8	4.0	373	373
20+78	TO	26+50	10	572	636	0.2	1.0	89	89
RAMP A6									
-2+10	TO	+	18	210	420	0.1	0.6	59	59
+	TO	2+00	24	200	533	0.2	0.8	75	75
2+00	TO	10+60	16	860	1529	0.5	2.3	214	214
10+60	TO	11+55	19	95	201	0.1	0.3	28	28
RAMP A7									
-1+10	TO	+	12	110	147	0.0	0.2	21	21
+	TO	2+01	25	201	558	0.2	0.8	78	78
2+01	TO	15+15	16	1314	2336	0.7	3.5	327	327
15+15	TO	16+75	18	160	320	0.1	0.5	45	45
RAMP A8									
+	TO	2+58	8	258	229	0.1	0.3	32	32
2+58	TO	4+40	23	182	465	0.1	0.7	65	65
4+40	TO	18+62	16	1422	2528	0.8	3.8	354	354
18+62	TO	20+36	19	174	367	0.1	0.6	51	51
20+36	TO	24+50	16	414	736	0.2	1.1	103	103
24+50	TO	26+40	6	190	127	0.0	0.2	18	18
SUB-TOTAL				17330	29990	9.4	45.0	4199	4199

FILE NAME = c:\projects\ed26207\plan\pln26207a.dgn	USER NAME = alfordb	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 4/24/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
270	60-(1,2,3,4)RS-2	MADISON	193	21
		CONTRACT NO. 76A90		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		