

PATCHING SCHEDULE #1

LOCATION	STATION	LENGTH (FT)	WIDTH (FT)	TYPE II 16" (SY)	TYPE III 16" (SY)	DOWEL BARS (EA)	SAW CUTS (LIN. FT.)
EBDL	327+14	6	12	8.0		20.0	49.5
EBDL	332+42	6	12	8.0		20.0	49.5
EBDL	358+82	6	12	8.0		20.0	49.5
EBDL	374+66	10	12	13.3		20.0	57.5
EBDL	385+22	6	12	8.0		20.0	49.5
EBPL	385+22	6	12	8.0		20.0	49.5
EBDL	411+62	6	12	8.0		20.0	49.5
EBDL	411+62	6	12	8.0		20.0	49.5
EBDL	416+90	6	12	8.0		20.0	49.5
EBDL	416+90	6	12	8.0		20.0	49.5
EBDL	422+18	6	12	8.0		20.0	49.5
EBDL	422+18	6	12	8.0		20.0	49.5
EBDL	422+18	6	12	8.0		20.0	49.5
EBDL	422+71	6	12	8.0		20.0	49.5
EBDL	423+24	6	12	8.0		20.0	49.5
EBDL	423+76	6	12	8.0		20.0	49.5
EBDL	424+29	6	12	8.0		20.0	49.5
EBDL	424+82	6	12	8.0		20.0	49.5
EBDL	425+35	6	12	8.0		20.0	49.5
EBDL	425+88	6	12	8.0		20.0	49.5
EBDL	426+40	6	12	8.0		20.0	49.5
EBDL	426+93	6	12	8.0		20.0	49.5
EBDL	427+46	6	12	8.0		20.0	49.5
EBDL	427+46	6	12	8.0		20.0	49.5
EBDL	427+46	6	12	8.0		20.0	49.5
EBPL	427+46	6	12	8.0		20.0	49.5
EBPL	432+74	6	12	8.0		20.0	49.5
EBCL	432+74	6	12	8.0		20.0	49.5
EBDL	432+74	6	12	8.0		20.0	49.5
EBDL	438+02	8	12	10.7		20.0	53.5
EBDL	438+02	6	12	8.0		20.0	49.5
EBDL	443+30	6	12	8.0		20.0	49.5
EBDL	443+30	10	12	13.3		20.0	57.5
EBDL	453+86	10	12	13.3		20.0	57.5
EBDL	453+86	6	12	8.0		20.0	49.5
EBDL	456+50	6	12	8.0		20.0	49.5
EBDL	457+56	10	12	13.3		20.0	57.5
EBDL	464+42	10	12	13.3		20.0	57.5
EBDL	472+34	6	12	8.0		20.0	49.5
EBPL	469+70	6	12	8.0		20.0	49.5
EBCL	477+62	6	12	8.0		20.0	49.5
EBDL	485+54	6	12	8.0		20.0	49.5
EBDL	493+46	6	12	8.0		20.0	49.5
EBDL	493+46	6	12	8.0		20.0	49.5
EBDL	498+74	6	12	8.0		20.0	49.5
EBDL	500+85	6	12	8.0		20.0	49.5
EBDL	500+85	6	12	8.0		20.0	49.5
EBDL	501+38	6	12	8.0		20.0	49.5
EBDL	501+38	6	12	8.0		20.0	49.5
EBPL	506+66	6	12	8.0		20.0	49.5
EBCL	509+30	6	12	8.0		20.0	49.5
EBCL	513+52	6	12	8.0		20.0	49.5
EBDL	515+64	6	12	8.0		20.0	49.5
EBDL	516+69	6	12	8.0		20.0	49.5
EBDL	516+69	8	12	10.7		20.0	53.5
EBCL	516+69	6	12	8.0		20.0	49.5
EBDL	516+69	8	12	10.7		20.0	53.5
EBDL	516+69	8	12	10.7		20.0	53.5
EBPL	DITCH	6	12	8.0		20.0	49.5
WBDL	516+69	10	12	13.3		20.0	57.5
WBCL	516+69	10	12	13.3		20.0	57.5
WBDL	514+58	10	12	13.3		20.0	57.5
SUB TOTAL:				559.9	0	1260	3202.5

(CONTINUED) PATCHING SCHEDULE #2

LOCATION	STATION	LENGTH (FT)	WIDTH (FT)	TYPE II 16" (SY)	TYPE III 16" (SY)	DOWEL BARS (EA)	SAW CUTS (LIN. FT.)
WBCL	514+58	10	12	13.3		20.0	57.5
WBDL	514+05	6	12	8		20.0	49.5
WBDL	514+05	10	12	13.3		20.0	57.5
WBCL	511+94	6	12	8		20.0	49.5
WBPL	510+88	6	12	8		20.0	49.5
WBDL	510+88	6	12	8		20.0	49.5
WBCL	510+36	6	12	8		20.0	49.5
WBDL	510+36	6	12	8		20.0	49.5
WBDL	509+83	6	12	8		20.0	49.5
WBPL	509+83	6	12	8		20.0	49.5
WBPL	509+30	6	12	8		20.0	49.5
WBDL	509+30	10	12	13.3		20.0	57.5
WBCL	509+30	6	12	8		20.0	49.5
WBDL	509+30	10	12	13.3		20.0	57.5
WBDL	509+30	10	12	13.3		20.0	57.5
WBDL	507+72	10	12	13.3		20.0	57.5
WBDL	506+66	6	12	8		20.0	49.5
WBCL	506+66	6	12	8		20.0	49.5
WBDL	506+66	6	12	8		20.0	49.5
WBDL	506+66	10	12	13.3		20.0	57.5
WBDL	505+08	12	12		16	20.0	61.5
WBDL	505+08	10	12	13.3		20.0	57.5
WBDL	501+38	6	12	8		20.0	49.5
WBDL	501+38	6	12	8		20.0	49.5
WBCL	501+38	6	12	8		20.0	49.5
WBPL	498+74	6	12	8		20.0	49.5
WBDL	498+74	6	12	8		20.0	49.5
WBPL	498+74	6	12	8		20.0	49.5
WBCL	490+82	6	12	8		20.0	49.5
WBDL	490+82	6	12	8		20.0	49.5
WBCL	490+82	6	12	8		20.0	49.5
WBPL	490+82	6	12	8		20.0	49.5
WBDL	489+24	6	12	8		20.0	49.5
WBDL	489+24	6	12	8		20.0	49.5
WBPL	489+24	6	12	8		20.0	49.5
WBDL	485+54	6	12	8		20.0	49.5
WBDL	485+54	6	12	8		20.0	49.5
WBPL	485+54	6	12	8		20.0	49.5
WBPL	485+54	6	12	8		20.0	49.5
WBDL	482+90	6	12	8		20.0	49.5
WBDL	482+90	6	12	8		20.0	49.5
WBDL	482+90	6	12	8		20.0	49.5
WBPL	482+90	6	12	8		20.0	49.5
WBPL	480+26	6	12	8		20.0	49.5
WBCL	480+26	6	12	8		20.0	49.5
WBDL	480+26	6	17	11.3		30.0	64.5
WBDL	474+98	6	12	8		20.0	49.5
WBCL	474+98	6	12	8		20.0	49.5
WBDL	474+98	6	12	8		20.0	49.5
WBDL	474+98	6	12	8		20.0	49.5
WBDL	474+98	6	12	8		20.0	49.5
WBDL	469+70	6	12	8		20.0	49.5
WBDL	469+70	6	12	8		20.0	49.5
WBDL	469+70	6	12	8		20.0	49.5
WBDL	469+70	6	12	8		20.0	49.5
WBDL	469+70	6	12	8		20.0	49.5
WBDL	469+70	6	12	8		20.0	49.5
WBPL	464+42	6	12	8		20.0	49.5
WBDL	464+42	6	12	8		20.0	49.5
WBDL	464+42	10	12	13.3		20.0	57.5
WBDL	464+42	10	12	13.3		20.0	57.5
SUB TOTAL:				544.2	16	1250	3176

FILE NAME =  
c:\projects\ed86287\plan\pln86287a.dgn

USER NAME = sifordb

DESIGNED -  
DRAWN -

REVISED -  
REVISED -

PLOT SCALE = 50.0000' / IN.  
PLOT DATE = 4/24/2008

CHECKED -  
DATE -

REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE. 270	SECTION 60-(1,2,3,4)RS-2	COUNTY MADISON	TOTAL SHEETS 193	SHEET NO. 26
CONTRACT NO. 76A90				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				