

(CONTINUED) PATCHING SCHEDULE #3

LOCATION	STATION	LENGTH (FT)	WIDTH (FT)	TYPE II 16" (SY)	TYPE III 16" (SY)	DOWEL BARS (EA)	SAW CUTS (LIN. FT.)
WBPL	464+42	6	12	8		20.0	49.5
WBCL	464+42	6	12	8		20.0	49.5
WBDL	464+42	6	12	8		20.0	49.5
WBDL	459+14	6	12	8		20.0	49.5
WBDL	453+86	6	12	8		20.0	49.5
WBCL	453+86	6	12	8		20.0	49.5
WBDL	453+86	6	12	8		20.0	49.5
WBDL	453+33	10	12	13.3		20.0	57.5
WBPL	453+33	6	12	8.0		20.0	49.5
WBDL	451+22	6	12	8.0		20.0	49.5
WBDL	451+22	6	12	8.0		20.0	49.5
WBDL	450+69	6	12	8.0		20.0	49.5
WBDL	450+16	6	12	8.0		20.0	49.5
WBDL	449+64	6	12	8.0		20.0	49.5
WBDL	449+11	6	12	8.0		20.0	49.5
WBDL	448+58	6	12	8		20.0	49.5
WBDL	448+05	6	12	8		20.0	49.5
WBCL	448+05	6	12	8		20.0	49.5
WBPL	448+05	6	12	8.0		20.0	49.5
WBDL	447+52	6	12	8.0		20.0	49.5
WBPL	443+30	6	12	8.0		20.0	49.5
WBDL	443+30	6	12	8.0		20.0	49.5
WBDL	443+30	6	12	8.0		20.0	49.5
WBPL	440+66	6	12	8.0		20.0	49.5
WBDL	440+66	6	12	8.0		20.0	49.5
WBDL	440+13	6	12	8.0		20.0	49.5
WBCL	440+13	6	12	8.0		20.0	49.5
WBCL	438+02	6	12	8.0		20.0	49.5
WBPL	438+02	6	12	8.0		20.0	49.5
WBDL	438+02	6	12	8.0		20.0	49.5
WBCL	438+02	6	12	8.0		20.0	49.5
WBDL	424+82	6	12	8.0		20.0	49.5
WBDL	424+82	6	12	8.0		20.0	49.5
WBPL	424+82	6	12	8.0		20.0	49.5
WBDL	424+82	10	12	13.3		20.0	57.5
WBPL	423+76	10	12	13.3		20.0	57.5
WBPL	423+76	6	12	8.0		20.0	49.5
WBDL	422+18	6	12	8.0		20.0	49.5
WBDL	422+18	6	12	8.0		20.0	49.5
WBDL	422+18	6	12	8.0		20.0	49.5
WBDL	422+18	6	12	8.0		20.0	49.5
WBDL	422+18	6	12	8.0		20.0	49.5
WBDL	422+18	6	12	8.0		20.0	49.5
WBCL	419+54	6	12	8.0		20.0	49.5
WBDL	419+54	10	12	13.3		20.0	57.5
WBDL	419+54	10	12	13.3		20.0	57.5
WBCL	419+54	6	12	8.0		20.0	49.5
WBCL	416+90	6	12	8.0		20.0	49.5
WBCL	411+62	10	12	13.3		20.0	57.5
WBCL	411+62	10	12	13.3		20.0	57.5
WBDL	411+62	10	12	13.3		20.0	57.5
WBDL	411+62	10	12	13.3		20.0	57.5
WBCL	411+62	6	12	8.0		20.0	49.5
WBDL	411+62	6	12	8.0		20.0	49.5
WBDL	411+62	6	12	8.0		20.0	49.5
WBDL	411+62	12	12		16	20.0	61.5
WBDL	406+34	6	12	8.0		20.0	49.5
WBDL	406+34	6	12	8.0		20.0	49.5
WBDL	406+34	6	12	8.0		20.0	49.5
WBDL	406+34	6	12	8.0		20.0	49.5
SUB TOTAL:				546.9	16	1240	3169

(CONTINUED) PATCHING SCHEDULE #4

LOCATION	STATION	LENGTH (FT)	WIDTH (FT)	TYPE II 16" (SY)	TYPE III 16" (SY)	DOWEL BARS (EA)	SAW CUTS (LIN. FT.)
WBDL	385+22	6	12	8.0		20.0	49.5
WBDL	385+22	6	12	8.0		20.0	49.5
WBDL	385+22	6	12	8.0		20.0	49.5
WBDL	379+94	6	12	8.0		20.0	49.5
WBDL	379+94	6	12	8.0		20.0	49.5
WBDL	379+94	6	12	8.0		20.0	49.5
WBDL	374+66	6	12	8.0		20.0	49.5
WBDL	374+66	6	12	8.0		20.0	49.5
WBDL	374+66	6	12	8.0		20.0	49.5
WBDL	364+10	6	12	8.0		20.0	49.5
WBDL	358+82	6	12	8.0		20.0	49.5
SCHEDULE #4 SUB TOTAL:				88	0	220	544.5
SCHEDULE #3 SUB TOTAL:				546.9	16	1240	3169
SCHEDULE #2 SUB TOTAL:				544.2	16	1250	3176
SCHEDULE #1 SUB TOTAL:				559.9	0	1260	3202.5
GRAND TOTAL:				1739	32	3970	10092

FILE NAME =
c:\projects\ed6207\plan\p1n06207a.dgn

USER NAME = alfordb
PLOT SCALE = 50.0000' / IN.
PLOT DATE = 4/24/2008

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
270	60-1,2,3,4RS-2	MADISON	193	27
CONTRACT NO. 76A90				

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT