



Hanson Professional Services Inc.

FOUNDATION SCHEDULE OF QUANTITIES			
ITEM DESCRIPTION		ITEM QUANTITY	
IDOT CODE	DESIGNATION	UNITS	QUANTITY
*	MONUMENT - TYPE A FOUNDATION	EACH	1
*	MONUMENT - TYPE B FOUNDATION	EACH	1
*	MONUMENT - TYPE C FOUNDATION	EACH	1
*	PRECAST COLUMN WITH PLANTER FOUNDATION	EACH	2
*	PRECAST WALL - TYPE B FOUNDATION	FOOT	19.5
*	PRECAST WALL - TYPE C FOUNDATION	FOOT	6
*	PRECAST WALL - TYPE D FOUNDATION	FOOT	22.3
*	PLANTER TOWER FOUNDATION	EACH	3
*	GAZEBO FOUNDATION WITH SLAB ON GRADE	LUMP SUM	1

ROADWAY LIGHTING SCHEDULE OF QUANTITIES				
ITEM DESCRIPTION			ITEM QUANTITY	
IDOT CODE	DESIGNATION		UNITS	QUANTITY
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC		FOOT	160
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL		FOOT	55
* 81028050	CONDUIT, BORED AND PULLED, COILABLE NON-METALLIC, 1 1/2"		FOOT	1415
* 81400730	HANDHOLE, COMPOSITE CONCRETE		EACH	3
81702100	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 12		FOOT	225
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10		FOOT	5205
81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8		FOOT	2890
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6		FOOT	2315
81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4		FOOT	6645
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK		FOOT	160
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE		EACH	21
84200700	LIGHTING FOUNDATION REMOVAL		EACH	21
87900200	DRILL EXISTING HANDHOLE		EACH	9
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT		FOOT	1775
* X0323927	MAINTENANCE OF LIGHTING SYSTEM		EACH	1
* X8950130	MODIFY EXISTING LIGHTING CONTROLLER		EACH	1
* XX002184	PHOTOELECTRIC CONTROL		EACH	1
*	DECORATIVE LIGHT TYPE A		EACH	11
*	DECORATIVE LIGHT TYPE B		EACH	6
*	DECORATIVE LIGHT TYPE BI		EACH	1
*	DECORATIVE LIGHT TYPE C		EACH	12
*	LIGHT POLE FOUNDATION, TYPE I		EACH	18
*	LIGHT POLE FOUNDATION, TYPE II		EACH	12
*	ELECTRICAL WORK COMPLETE - SCENIC VISTA		LUMP SUM	1
*	ELECTRICAL WORK COMPLETE - GATEWAY MONUMENT		LUMP SUM	1
*	DECORATIVE LIGHT TYPES A AND C - MATERIAL ONLY		LUMP SUM	1

UTILITY CONTACTS

UTILITY NAME	TYPE	CONTACT	PHONE NUMBER
COMMONWEALTH EDISON CO. 123 ENERGY AVENUE ROCKFORD, ILLINOIS 61109	ELECTRICAL	MIKE LENOX	(815) 490-2869
CITY OF DEKALB WATER RESOURCE DIVISION 1216 MARKET ST. DEKALB, IL 60115	WATER	BRYAN FAIVRE	(815) 748-2050
DEKALB SANITARY DISTRICT 303 HOLLISTER AVE PO BOX 624 DEKALB, IL 60115-0624	SANITARY	MIKE ZIMA	(815) 758-3513
COMCAST CABLE 688 INDUSTRIAL DRIVE ELMHURST, IL 60126	TV	TED WYMAN	(630) 600-6349
VERIZON NORTH, INC 112 W. ELM ST. SYCAMORE, IL 60178	COMMUNICATIONS	JOEL PLAPP	(815) 895-1415
NICOR GAS UTILITY CONSULTANT 1844 FERRY RD NAPERVILLE, IL 60563	GAS	CONSTANCE LANE	(630) 388-3830

DESIGNED CPS  
DRAWN MWH  
CHECKED CPS  
DATE 04/10/08

REVISED  
REVISED  
REVISED  
REVISED

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULES  
EAST LINCOLN HIGHWAY  
LIGHTING AND STREETSCAPE  
DEKALB, IL  
SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 567 SECTION 06-00173-00-LT COUNTY DEKALB TOTAL SHEETS 41 CONTRACT NO. 8 ILLINOIS ITP 32025