CONTRACT NO. 94533

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	1YRS, 2ZRS-1	CRAWFORD	378	27
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PIPE CULVERT SCHEDULE

LOCATION		TYPE	TRENCH BACKFILL	PIPE CULVERTS															PRECAST REINFORCED CONCRETE FLARED END SECTIONS						END SECTIONS								PIPE TEES			INLETS
				RCCP						CLASS D																								375 PIPE WITH	600 PIPE WITH	750 PIPE WITH	TYPE A,
STATION	RT/LT /AR		CUBIC METER	TYPE 1 375 METER	TYPE 1 450 METER	TYPE 1 600 METER	TYPE 1 750 METER	TYPE 1 900 METER	TYPE 1 1500 METER	TYPE 1 300 METER	TYPE 1 375 METER	TYPE 1 450 METER	TYPE 1 525 METER	TYPE 1 600 METER	TYPE 1 675 METER	TYPE 1 750 METER	TYPE 1 900 METER	TYPE 1 1050 METER	375 EACH	450 EACH	600 EACH	750 EACH	900 EACH	1500 EACH	300 EACH	375 EACH	450 EACH	525 EACH	600 EACH	675 EACH	750 EACH	900 EACH	1050 EACH	300 RISER EACH	375 RISER EACH	375 RISER EACH	TY 8 GRATE EACH
RURAL																																				
STA 0+952.000	RT	PIPE CULVERTS										10.36															2									
STA 1+201.500	LT	PIPE CULVERTS										8.84															2									
STA 1+392.000	LT	PIPE CULVERTS	6.91		18.29															2															
STA 1+465.000	LT	PIPE CULVERTS												10.36																						
STA 1+465.000	RT	PIPE CULVERTS												12.50																						
STA 1+595.600	RT	PIPE CULVERTS										10.97															2									
STA 1+755.200	LT	PIPE CULVERTS										10.67															2									
STA 1+764.500	RT	PIPE CULVERTS										15.85															2									
STA 2+196.000	LT	PIPE CULVERTS												11.58															2							
STA 2+403.300	RT	PIPE CULVERTS	20.15						17.37															2												
STA 2+534.000	LT	PIPE CULVERTS									13.41															2										
OBLONG - SEE STORM SEWER SCHEDULE																																				
RURAL																																				
STA 4+529.000	RT	PIPE CULVERTS										16.76															4									
STA 4+583.500	LT	PIPE CULVERTS										17.07															2									
STA 4+601.300	RT	PIPE CULVERTS										42.68															4									
STA 4+618.800	LT	PIPE CULVERTS										15.54															2									
STA 5+141.000	LT	PIPE CULVERTS									22.56															2										
STA 5+193.700	LT	PIPE CULVERTS									15.85															2										
STA 5+194.097	RT	PIPE CULVERTS	6.40	22.56															2																	
STA 5+295.000	AR	PIPE CULVERTS	7.14			17.07															2															
STA 5+345.500	LT	PIPE CULVERTS										13.41															2									
STA 5+345.500	RT	PIPE CULVERTS									14.94															2										
STA 5+466.700	LT	PIPE CULVERTS									16.46															2										
STA 5+618.000	RT	PIPE CULVERTS									21.03															2										
STA 5+621.500	LT	PIPE CULVERTS										16.46															2									
STA 5+651.500	RT	PIPE CULVERTS									22.56															2										
STA 5+720.000	LT	PIPE CULVERTS												12.19																						
STA 5+771.700	LT	PIPE CULVERTS													10.67																					
STA 5+938.000	RT	PIPE CULVERTS												10.36															2							
STA 6+084.500	RT	PIPE CULVERTS											13.41															2								
STA 6+140.500	RT	PIPE CULVERTS											12.19															2								
STA 6+180.600	LT	PIPE CULVERTS												9.45															2							
STA 6+181.600	RT	PIPE CULVERTS											10.97															2								
STA 6+441.000	RT	PIPE CULVERTS												9.42															2							
STA 6+444.936	LT	PIPE CULVERTS	2.04			11.64															2															
STA 6+483.500	RT	PIPE CULVERTS	5.38	16.76															2																	
STA 6+500.000	LT	PIPE CULVERTS									17.68															2										
STA 6+562.500	LT	PIPE CULVERTS									14.63															2										
STA 6+572.500	RT	PIPE CULVERTS									16.46															2										
STA 6+592.700	LT	PIPE CULVERTS									15.54															2										
STA 6+632.800	RT	PIPE CULVERTS									14.02															2										
STA 6+636.700	LT	PIPE CULVERTS									14.02															1										
STA 6+643.500	LT	PIPE CULVERTS								2.44															1									1			
STA 6+652.100	LT	PIPE CULVERTS									17.68															1										
STA 6+746.500	RT	PIPE CULVERTS										12.50															2									
STA 6+784.500	RT	PIPE CULVERTS										12.80															2									
STA 6+819.200	RT	PIPE CULVERTS										14.33															2									
STA 6+907.000	RT	PIPE CULVERTS												9.75															2							
STA 7+015.000	LT	PIPE CULVERTS									17.98															2										
STA 7+071.000	RT	PIPE CULVERTS										17.07															2									
STA 7+177.000	RT	PIPE CULVERTS									20.73															2										
STA 7+291.800	LT	PIPE CULVERTS						10.36																								2				
STA 7+328.600	LT	PIPE CULVERTS															14.94															2				
STA 7+392.900	LT	PIPE CULVERTS															11.89															2				
STA 7+471.600	LT	PIPE CULVERTS														9.14																2				
STA 7+478.000	RT	PIPE CULVERTS														12.80																2				

CONTINUED

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

PIPE CULVERT SCHEDULE

SCALE | DRAWN BY KOJ

DATE APRIL 18, 2008 | CHECKED BY RGH

H. M. & G. NO. 4420

PLOT DATE = 4/18/2008
FILE NAME = H:\4420\70827_sch_pipe culvert.dgn