CONTRACT NO. 94533

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	1YRS, 2ZRS-1	CRAWFORD	378	37
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

STORM SEWER SCHEDULE (CONTINUED)

UPSTREAM STRUCTURE				DOWNSTREAM STRUCTURE				TRENCH BACKFILL	STORM SEWERS, CLASS B	STORM SEWERS, CLASS A					RESTRICTED DEPTH MANHOLES							INLETS, TYPE A			INLETS, TYPE B	
										TYPE 1						TYPE 1 FRAME, CLOSED LID				TYPE 3 FRAME AND GRATE							
STR #	LOCATION			STR #	LOCATION				TYPE 1													TYPE 3 FRAME AND GRATE	TYPE 8 FRAME AND GRATE	TYPE 11 FRAME AND GRATE	TYPE 3 FRAME AND GRATE	TYPE 8 GRATE
	STATION	OFFSET METER	LT/RT		STATION	OFFSET METER	LT/RT	M2080150 CU M	M5500215 150MM METER	M5500430 300MM METER	M5500450 450MM METER	M5500465 600MM METER	M5500475 750MM METER	M5500485 900MM METER	M5500495 1050MM METER	M6022110 1.2 M EACH	M6022210 1.5 M EACH	M6022310 1.8 M EACH	M6023255 2.4 M EACH	M6022115 1.2 M EACH	M6022215 1.5 M EACH	M6022315 1.8 M EACH	60235700 EACH	60236200 EACH	60236800 EACH	60240220 EACH	60240301 EACH
EX	4+379.915	9.016	LT	526	4+403.640	7.860	LT	9.287		22.934																
526	4+403.640	7.860	LT	527	4+403.640	4.475	RT	5.610		11.516																1
527	4+403.640	4.475	RT	528	4+403.640	6.200	RT	0.167		0.581															1	
529	4+451.600	4.475	RT	530	4+451.600	11.000	RT	2.258		5.563												1				
TOTALS								2945.228	7.200	705.053	242.233	760.803	180.086	319.795	193.778	9.000	17.000	10.000	1.000	2.000	1.000	5.000	84.000	10.000	2.000	34.000	2.000
TOTALS ROUNDED FOR SUMMARY SHEET								2946	7.2	705.1	242.3	760.9	180.1	319.8	193.8	9	17	10	1	2	1	5	84	10	2	34	2

FOR MORE ITEMS, SEE NEXT SHEET

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

STORM SEWER SCHEDULE

SCALE

DRAWN BY KOJ

DATE APRIL 18, 2008

CHECKED BY RGH

H. M. & G. NO. 4420

PLOT DATE = 4/18/2008
FILE NAME = H:\4420\70803_sch_storm sewer.dgn

HENRY, MEISENHEIMER & GENDE, INC., 1075 LAKE RD., P.O. BOX 70, CARLYLE, ILLINOIS 62231 (618)-594-3711 WWW.HMGENGINEERS.COM