

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	1YRS, 2ZRS-1	CRAWFORD	378	45
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

RURAL ENTRANCE SCHEDULE - CONTINUED

LOCATION				WIDTH	LENGTH			RADIUS	AGGREGATE BASE COURSE, TYPE B	HOT-MIX ASPHALT BASE COURSE	AGGREGATE SURFACE COURSE, TYPE B	BITUMINOUS MATERIALS (PRIME COAT)		AGGREGATE (PRIME COAT)	INCIDENTAL HOT-MIX ASPHALT SURFACING		PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT		
												PRIOR TO BINDER/BASE COURSE	PRIOR TO SURFACE COURSE		50MM	75MM	150 MM	200 MM	
STATION	LT/RT	TYPE	EXISTING MATERIAL	W1	L1	L2		150MM	200MM	150MM		M4080100	M4080300	M4080500	M4230150	M4230200			
				METER	METER	METER	METER	M TON	SQ. M	M TON		LITER	LITER	M TON	M TON	M TON	SQ. M	SQ. M	
STA 14+763.300	RT	PE	BITUMINOUS	5.0	6.30	8.64	6	29.00				120.82				14.50			
STA 14+770.800	LT	PE	AGGREGATE	4.2	6.30	8.64	5 & 6	11.96		13.06		49.84				5.98			
STA 14+803.300	LT	PE	AGGREGATE	3.6	6.30	8.64	6	10.73		11.19		44.70				5.36			
STA 14+861.800	RT	PE	AGGREGATE	3.6	6.30	8.64	6	10.73		11.19		44.70				5.36			
STA 14+886.300	RT	PE	AGGREGATE	3.6	6.30	8.64	6	10.73		11.19		44.70				5.36			
STA 14+926.300	LT	PE	BITUMINOUS	3.6	6.30	8.64	6	21.92				91.34				10.96			
STA 14+926.300	RT	FE	DIRT	3.6	6.30	8.64	6			17.52									
STA 14+981.900	LT	PE	AGGREGATE	3.6	6.30	8.64	6	10.73		11.19		44.70				5.36			
STA 15+062.400	LT	ROAD	OIL & CHIP	See Plans	15.30	6.35	15		256.21			384.31	89.67	0.384	30.74				
STA 15+062.400	RT	ROAD	BITUMINOUS	See Plans	15.30	6.35	15		258.07			387.11	90.32	0.387	30.97				
STA 15+232.300	LT	CE	AGGREGATE	10.6	6.30	8.64	6		67.60	32.96		101.40	23.66	0.101	8.11				
STA 15+321.000	LT	CE	CONC/AGG	10.6	6.30	8.64	6											177.38	
STA 15+353.800	LT	CE	AGGREGATE	4.3	6.30	8.64	6		33.58	13.37		50.37	11.75	0.050	4.03				
STA 15+450.800	RT	PE	AGGREGATE	7.2	6.30	4.07	6	17.73		10.54		73.86			8.86				
STA 15+454.800	LT	CE	CONC/AGG	10.6	6.30	8.64	6			32.96								85.83	
STA 15+509.800	LT	CE	AGGREGATE	10.6	6.30	8.64	6			32.96								85.83	
STA 15+511.800	RT	PE	AGGREGATE	4.0	6.30	8.64	6	11.51		12.44		47.94			5.75				
<b>URBAN</b>																			
STA 15+595.800	LT	PE	AGGREGATE	7.2	6.30	8.64	6	17.73		22.39		73.86			8.86				
STA 15+660.800	LT	CE	BITUMINOUS	7.2	6.30	5.59	6		89.49			134.23	31.32	0.134	10.74				
STA 15+661.300	RT	ROAD	OIL & CHIP	5.8	9.30	2.60	9		109.19			163.78	38.21	0.164	13.10				
STA 15+723.100	RT	PE	BITUMINOUS	6.0	6.30	8.64	6	34.05				141.87			17.02				
STA 15+773.300	RT	ROAD	OIL & CHIP	5.9	9.30	2.35	9		114.80			172.20	40.18	0.172	13.78				
STA 15+870.300	RT	PE	AGGREGATE	3.6	6.30	8.64	6	10.73		11.19		44.70			5.36				
STA 15+871.400	LT	ROAD	AGGREGATE	3.6	9.30	2.59	9	20.45		3.36		85.21			10.22				
STA 15+890.000	LT	PE	AGGREGATE	3.6	6.30	22.41	6	10.73		29.04		44.70			5.36				
STA 15+916.600	RT	PE	BITUMINOUS	3.6	6.30	8.64	6	21.92				91.34			10.96				
STA 15+931.300	RT	PE	BITUMINOUS	3.6	6.30	8.64	6	21.92				91.34			10.96				
STA 15+960.300	LT	PE	BIT/AGGREGATE	10.3	6.30	8.64	6	55.78				232.41			27.89				
<b>TOTALS</b>									1,775.69	7,435.98	2,563.11	11,153.97	10,001.31	11.15	892.32	883.88	332.30	1,757.84	
<b>TOTALS ROUNDED FOR SUMMARY SHEET</b>									1,776	7,436	2,564	21,156	12	1,777	333	1,758			

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		RURAL ENTRANCE SCHEDULE
SCALE	NO SCALE	DRAWN BY KOJ
DATE	APRIL 18, 2008	CHECKED BY RGH

PLOT DATE = 4/18/2008  
FILE NAME = H:\4428\70042\_ent\_r.dgn

H. M. & G. NO. 4420