



SURVEY TIE POINT SCHEDULE

CONTROL POINT NO.	STATION	DISTANCE, OFFSET	DESCRIPTION	NORTHING	EASTING	ELEVATION
LEGION STREET						
CP-12	22+03.20	37.45' RT	IRON BAR	645,870.4600	2,285,987.1114	499.70
CP-13	25+78.23	27.29' RT	IRON BAR	645,931.3488	2,286,369.3759	508.50
CP-14	30+89.60	21.45' RT	IRON BAR	646,310.7209	2,286,716.8553	509.77
CP-15	32+74.19	28.74' RT	IRON BAR	646,439.9040	2,286,847.2955	509.15
CP-16	36+91.15	10.96' LT	PK NAIL	646,771.4666	2,287,104.7430	508.79
CP-25	23+56.72	24.34' RT	NAIL	645,884.2848	2,286,140.5763	502.15
CP-27	35+17.39	18.94' LT	PK NAIL	646,649.7988	2,286,980.4352	509.38

PLAN	SURVEYED	DATE
	PLOTTED	
	NOTED	
	BY	
	NO. OF WAYS CHECKED	
	CADD FILE NAME	

PROFILE	SURVEYED	DATE
	PLOTTED	
	NOTED	
	BY	
	NO. OF WAYS CHECKED	
	STRUCTURE NOTATIONS CHRD	

PLOT DATE = 5/5/2008
 FILE NAME = #FILE#
 PLOT SCALE = #SCALE#
 USER NAME = #USER#

