

100% STATE

CONSTRUCTION CODE							C11	C12	C02	C13	C14	C15		
A01	C01	C02	C03	C04	C05	C06	11	12	13	14	15	16	17	18

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	TRAFFIC SIGNAL																
				URBAN																
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6																
67100100	MOBILIZATION	L SUM	1	1																
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1																
* 72000100	SIGN PANEL - TYPE 1	SD FT	1	1																
* 72400310	REMOVE SIGN PANEL - TYPE 1	SD FT	1	1																
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	65	21	6	2	2	1	1	1	1	1	3	14	2	4	2	1	1	1
△ 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1	1																
87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	11	10										1						
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	56	16	6		1	4	1		6	4		5	2	4		2		5
87502490	TRAFFIC SIGNAL POST, GALVANIZED STEEL 15 FT.	EACH	3	1												2				
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	33	15	4			2	2					5	2			2		1
87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	8	5										1	2					
88001640	SIGNAL HEAD, LED, 3-FACE, 2-3 SECTION, 1-4 SECTION, BRACKET MOUNTED	EACH	1													1				
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	56	11	23			2	3			2		8		4		2		1
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	57	18	5			4			4	4		9	2	7				4

\*Specialty Items

Rev. 6-4-14

FILE NAME = D:\6082\ht-5001.dgn	USER NAME = SJohnson	DESIGNED - PHL	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES (SHEET 2 OF 6)	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 40.0000' / 1" in.	DRAWN - PHL	CHECKED - BKS	REVISED -			2014-007TS	COOK	88	7	
PLOT DATE = 3/21/2014	DATE -	REVISED -				CONTRACT NO. 60X82	ILLINOIS FED. AID PROJECT			
Default						SCALE:   SHEET OF SHEETS   STA. TO STA.				