

GENERAL NOTES

FOR STABILIZATION, ALL TYPE III BARRICADES WILL REQUIRE A MINIMUM OF FOUR SAND BAGS PER BARRICADE.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER SHOWN IN THE LIST OF STANDARDS OR THE COPY INCLUDED IN THESE PLANS.

LOCATION NO. 6
SN. 050-0079

1: EXISTING "ARCH" STRUCTURAL STEEL SHALL NOT BE INCLUDED IN THIS WORK.

2: THE CONTRACTOR SHALL CONDUCT HIS WORK OPERATIONS SO THAT NO EQUIPMENT, MATERIALS OR PERSONNEL ENCROACH WITHIN AN AREA FROM THE BOTTOM OF THE DECK TO THE TOP OF TRACKS THROUGH SPAN 3 AND SPAN 4.

COMMITMENTS

FUNCTIONAL CLASSIFICATIONS

LOCATION 1

SN 032-0099
FUNCTIONAL CLASSIFICATION
URBAN OTHER ARTERIAL
F.A.P. ROUTE 326 (IL 170)
2015 ADT 18000
P.V. 86.1% S.U. 6.1% M.U. 7.8%

LOCATION 2

SN 050-0246
FUNCTIONAL CLASSIFICATION
RURAL MINOR ARTERIAL
F.A.P. ROUTE 786 (IL 170)
2015 ADT 6400
P.V. 89.1% S.U. 4.7% M.U. 6.2%

LOCATION 3

SN 050-0219
FUNCTIONAL CLASSIFICATION
MAJOR COLLECTOR
F.A.S. ROUTE 268 (CH 15)
2016 ADT 4450
P.V. 90.5% S.U. 7.9% M.U. 1.6%

LOCATION 4

SN 050-0180
FUNCTIONAL CLASSIFICATION
URBAN OTHER ARTERIAL
F.A.P. ROUTE 68 (IL 23/71)
2015 ADT 27300
P.V. 96.4% S.U. 2.0% M.U. 1.6%

LOCATION 5

SN 050-0237
FUNCTIONAL CLASSIFICATION
RURAL MINOR ARTERIAL
F.A.P. ROUTE 619 (IL 351)
2015 ADT 5750
P.V. 95.1% S.U. 3.5% M.U. 1.4%

LOCATION 6

SN 050-0079
FUNCTIONAL CLASSIFICATION
URBAN OTHER ARTERIAL
F.A.P. ROUTE 46 (IL 251)
2015 ADT 7250
P.V. 85.2% S.U. 11.0% M.U. 3.8%

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DISTRICT THREE
AS BUILT INFORMATION

SUPERVISING CONSTRUCTION FIELD ENGINEER

RESIDENT ENGINEER / TECHNICIAN

START & END DATES
OF CONSTRUCTION:

INSPECTORS:

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DISTRICT THREE

PREPARED BY: _____
DISTRICT STUDIES & PLANS ENGINEER

DATE: _____

EXAMINED BY: _____
DISTRICT CONSTRUCTION ENGINEER

DISTRICT MATERIALS ENGINEER

DISTRICT OPERATIONS ENGINEER

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

SCALE: _____ SHEET 1 OF 1 SHEETS STA. _____ TO STA. _____

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	D3 BRIDGE WASHING 2019-1	GRUNDY/LASALLE	30	2
CONTRACT NO. 66K10				
ILLINOIS			FED. AID PROJECT	

MODEL: Default
 FILE: \\nas0101.pwd.state.il.us\pub\baronm.d\at\links\gov\p\WIDOT\Documents\IDOT_Offices\District 3\Projects\0366K10\CADD\0366K10-drawings.dgn