

TEMPORARY INFORMATION SIGNING

NOTES:

- 1. USE 6" D BLACK LETTERING ON FLUORESCENT ORANGE BACKGROUND.
- 2. ERECT SIGNS AT LOCATIONS IN ADVANCE OF THE "ROAD CONSTRUCTION AHEAD" SIGNS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN()WITH INSTALLED PANEL()A MINIMUM OF ONE WEEK PRIOR TO THE START OF THE LANE CLOSURE.
- 4. REMOVE PANEL 2 ON THAT DATE.
- 5. SEE SPECIAL PROVISION "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. WILL BE PAID FOR PER SQ FT AS "TEMPORARY INFORMATION SIGNING".
 EACH SIGN = 21 SQ FT AND THE DATE PANEL WILL NOT BE MEASURED SEPARATELY FOR PAYMENT.

USER NAME = woodshankrl	DESIGNED	-	ECP	REVISED	
	DRAWN	-	ECP	REVISED	
PLOT SCALE = 100.0000 ' / in.	CHECKED	-	RW	REVISED	
PLOT DATE = 3/18/2019	DATE	-	1/29/19	REVISED	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

							F.A RTE.		SECTIO	N	COUNTY	TOTAL SHEETS	SHEET NO.	
TEMPORARY INFORMATION SIGNING						VAR.	D3 BRIDGE	WASHIN	IG 2019-1	GRUNDY/LASALLE	30	30		
												CONTRACT	VO. 66k	(10
	SHEET	1	OF	1	SHEETS	STA.	TO STA.				ILLINOIS E	D. AID PROJECT		