

# SUMMARY OF QUANTITIES - CONT

COUNTY:	JEFFERSON CO
ROUTE:	IL 142
FUNDING:	80% FED / 20% STATE
LOCATION:	ROADWAY

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	
				URBAN 0005	RURAL 0005
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	675	675	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	300	300	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	96	72	24
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	279	100	179
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	279	100	179
X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	SQ FT	15,773	4,238	11,535
Z0033700	LONGITUDINAL JOINT SEALANT	FOOT	17,122	4,117	13,005
Z0034105	MATERIAL TRANSFER DEVICE	TON	8,473	2,839	5,634
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	

\* SPECIALTY ITEM



△ REV. 6-3-2019

MODEL: Default  
 FILE: M:\MIS: P:\uplanroom.dat\illinois.gov\PIWDOT\Documents\DOT\_Offices\District\_9\Projects\78729\CAD\Sheet\078729-Sheets.dgn

USER NAME = handyc	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 4/16/2019	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
849	(12,112,113)RS-5	JEFFERSON	23	7
CONTRACT NO. 78729			ILLINOIS FED. AID PROJECT	