SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: STATE URBAN 90% FEDERAL 10% STATE 0004	TRAFFIC 90% FEDERAL 7.5% STATE 2.5% VILLAGE 0021	TRAFFIC EVP 100% VILLAGE 0021	BIKE PATH 90% FEDERAL 10% VILLAGE 0028	FIRE HYDRANT 100% VILLAGE 0043	
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1					
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	1	1					
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	4	4					
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	2.5	2.5					
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1055	1055					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	565	565					
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	3490	3490					
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1152	1152					
66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1					
66900530	SOIL DISPOSAL ANALYSIS	EACH	4	4					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	25	25					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	500	500					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	425.7	425.7					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: STATE URBAN 90% FEDERAL 10% STATE 0004	TRAFFIC 90% FEDERAL 7.5% STATE 2.5% VILLAGE 0021	TRAFFIC EVP 100% VILLAGE 0021	BIKE PATH 90% FEDERAL 10% VILLAGE 0028	FIRE HYDRANT 100% VILLAGE 0043	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6020	6020					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1284	1284					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	167	167					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	367	367					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	172	172					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1235	1235					
* 72000100	SIGN PANEL - TYPE 1	SQ FT	15		15				
* 72000200	SIGN PANEL - TYPE 2	SQ FT	30		30				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	425.7	425.7					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6020	6020					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1284	1284					
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	167	167					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	367	367					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	172	172					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	70	70					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	150	150					

FILE NAME = c:\pw_work\pwidot\mldyja\dms32836\P156808-Design.dgn	USER NAME = mldyja	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	US RTE 30 (LINCOLN HWY) AT CENTRAL AVE. SUMMARY OF QUANTITIES	F.A.P. RTE. 353	SECTION 23-N-4	COUNTY COOK	TOTAL SHEETS 68	SHEET NO. 6
		DRAWN -	REVISED -					CONTRACT NO. 60L21		
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -		SCALE: SHEET NO. 3 OF 5 SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		
	PLOT DATE = 3/29/2012	DATE -	REVISED -							

* SPECIALTY ITEMS