

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 0004 90% Fed. 10% State	TRAFFIC SIGNALS 0021 90% Fed. 5% State 5% Village					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 0004 90% Fed. 10% State	TRAFFIC SIGNALS 0021 90% Fed. 5% State 5% Village				
78300200	RAISED REFLECTIVE PAVEMENT MARKER	EACH	40	40						87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1584		1584				
	REMOVAL																		
80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1					87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	31		31				
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	772		772					87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	4		4				
81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	68		68					87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT	EACH	1		1				
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	88		88					87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT	EACH	1		1				
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	307		307					87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT	EACH	1		1				
81400100	HANDHOLE	EACH	1		1					87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT	EACH	1		1				
81400200	HEAVY-DUTY HANDHOLE	EACH	8		8					87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16		16				
81400300	DOUBLE HANDHOLE	EACH	1		1					87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4				
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1					87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	10		10				
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	812		812					87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	35		35				
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1669		1669														

\*

\* Specialty Items