

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 0004 90% Fed. 10% St.	TRAFFIC SIGNALS 0021 90% Fed. 5% State 5% Village			CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 0004 90% Fed. 10% State	TRAFFIC SIGNALS 0021 90% Fed. 5% State 5% Village		
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	3		3			X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	6	6			
88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2		2			X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	5	5			
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	5		5			X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	100	100			
88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1		1			X5537900	STORM SEWERS TO BE CLEANED 15"	FOOT	50	50			
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1		1			X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	2	2			
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	8		8			X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	1		1		
88500100	INDUCTIVE LOOP DETECTOR	EACH	8		8			Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	50	50			
88600100	DETECTOR LOOP, TYPE I	FOOT	848		848			Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1			Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	5	5			
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1			Z0023202	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	10	10			
89502380	REMOVE EXISTING HANDHOLE	EACH	8		8			Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	102.8	102.8			
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9		9			Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1		1		
								X87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING, NO. 6, 1C L CONDUCTOR	FOOT	535		535		
								X66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	2050	2050			
								X66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1			
								X66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1			

FILE NAME =	USER NAME = gulloume.p	DESIGNED -	REVISED -
ca:\pwr\work\pwr\gulloume.p\40301782-D159311-Design.dgn		DRAWN -	REVISED -
PLOT SCALE = 100,0000' / 1"		CHECKED -	REVISED -
PLOT DATE = 4/3/2012		DATE -	REVISED -

STATE OF ILLINOIS
** Specialty Items*
Δ 100% State (NP)

SUMMARY OF QUANTITIES			
SHEET NO.	OF	SHEETS	STA. TO STA.

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2711	27-N-2	LAKE	53	7
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60P63	

Rev