

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
VARIOUS	2011-059-I	COOK	44	6

Contract 60P77

SUMMARY OF QUANTITIES						
				URBAN 100% STATE	CONSTRUCTION TYPE CODE 0040	
Code No	Description	Unit	Total Quantities	0021		
20200100	EARTH EXCAVATION	CU YD	15	15		
20700220	POROUS GRANULAR EMBANKMENT	CU YD	0.6	0.6		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	29	29		
25000210	SEEDING, CLASS 2A	ACRE	0.01	0.01		
28001100	TEMPORARY EROSION CONTROL BLANKET	SQ YD	22	22		
42001300	PROTECTIVE COAT	SQ YD	166	166		
44213200	SAW CUTS	FOOT	201	201		
44213202	TIE BARS 1"	EACH	248	248		
50102400	CONCRETE REMOVAL	CU YD	37	37		
50300225	CONCRETE STRUCTURES	CU YD	35.4	35.4		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	3.5	3.5		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	540	540		

SHEET 1 OF 2

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

Rev.