DRAINAGE PIPE SCHEDULE CON'T

Pipe ID	Pipe Diameter (inches)	Length (ft)	Slope %	Upstream Structure	Downstream Structure	Upstream Rim Elevation	Downstream Rim Elevation	Upstream Depth	Upstream Invert	Downstream Invert	20800150 Trench Backfill	550A0340 Storm Sewers, Class A, Type 2 12"	Z0056608 Storm Sewers, (Water Main Requirements) 12"	X0322916 Proposed Storm Sewer Connection to Existing Storm Sewer	X0322917 Proposed Storm Sewer Connection to Existing Manhole	X5538200 Storm Sewers To Be Cleaned 24"	X5538400 Storm Sewers To Be Cleaned 30"	X5538600 Storm Sewers To Be Cleaned 36"	X5538700 Storm Sewers To Be Cleaned 42"	X5538800 Storm Sewers To Be Cleaned 48"	X5538900 Storm Sewers To Be Cleaned 54"
											CY YD	FOOT	FOOT	EACH	EACH	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
TL-12	36	399																399			
P12-2	12	22	1%	S12-3	S12-2	613.90	613.90	4.00	609.90	609.68	12	22									
P12-1	12	63	1%	S12-2	S12-1	613.90	614.30	2.80	611.10	610.47	26	63									
P12-4	12	51	1%	S12-4	S12-1	613.90	614.30	0.10	610.37	609.86	26		51								
TL-13	36	427																427			
P13-2	12	41	1%	S13-2	S13-1	613.92	613.73	3.40	610.52	610.11	20		41								
P13-1	12	8	1%	S13-1	C13-1	613.73	-	0.10	610.01	609.93	4	8		1							
P13-4	12	33	1%	S13-4	S13-3	613.60	613.30	2.95	610.65	610.32	13		33								
P13-3	12	17	1%	S13-3	C13-3	613.30	-	0.10	610.22	610.05	7	17		1							
P13-6	12	32	1%	S13-6	S13-5	613.40	613.40	2.60	610.80	610.48	11		32								
P13-5	12	11	1%	S13-5	C13-5	613.40	-	0.10	610.38	610.27	4	11		1							
P13-7	12	36	0.5%	S13-8	S13-7	613.50	613.50	2.80	610.70	610.52	13		36								
TL-14	30	79															79				
P14-1	12	33	0.5%	S14-2	S14-1	612.80	613.20	1.75	611.05	610.89	6		33								
P14-3	12	33	0.5%	S14-4	S14-3	612.80	613.20	1.35	611.45	611.29	4		33								
P14-6	12	32	0.5%	S14-6	S14-5	613.70	613.60	2.15	611.55	611.39	8		32								
P14-5	12	7	0.5%	S14-5	C14-5	613.60	-	0.10	611.29	611.26	2	7		1							
TL-15	24	254														254					
P15-2	12	32	0.5%	S15-2	S15-1	613.30	613.70	1.64	611.66	611.50	6		32								
P15-1	12	16	0.5%	S15-1	C15-1	613.70	-	0.12	611.38	611.30	4		16	1							
P16-2	12	39	1%	S16-2	S16-1	613.80	614.00	4.00	609.80	609.41	22	39									
P16-1	12	17	1%	S16-1	C16-1	614.00	-	0.10	609.31	609.14	11		17	1							
P16-4	12	32	1%	S16-4	S16-3	613.90	614.60	4.00	609.90	609.58	18	32									
P16-3	12	24	1%	S16-3	C16-3	614.60	-	0.10	609.48	609.24	17		24	1							
TL-2	54	346																			346
TL-3	54	244																			244
										TOTAL	**1033**	**1443**	**495**	**27**	**1**	**254**	**79**	**826**	**407**	**1652**	**1077**

•(0102-683K, ETC&0507-635K)RS-1

FILE NAME =	DESIGNED - AAF	REVISED -
...\D160T38-sht-ADV-schedule-03.dgn	DRAWN - TMB	REVISED -
USER NAME = tblank	CHECKED - JMM	REVISED -
PLOT DATE = 5/4/2012	DATE - 3/23/2012	REVISED -

benesch engineers · scientists · planners

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NTS | SHEET NO. 3 OF 3 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
372	•	COOK	40	12

CONTRACT NO. 60T38

ILLINOIS FED. AID PROJECT