

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN - 90% FEDERAL, 10% STATE		
				0004		0011
				STUENKEL ROAD	I-57	SN099-0526
50157300	PROTECTIVE SHIELD	SO YD	449			449
50200100	STRUCTURE EXCAVATION	CU YD	485			485
50300225	CONCRETE STRUCTURES	CU YD	349.6			349.6
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1056.0			1056.0
50300260	BRIDGE DECK GROOVING	SO YD	1862			1862
50300280	CONCRETE ENCASEMENT	CU YD	25.1			25.1
50300300	PROTECTIVE COAT	SO YD	3541			3541
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1.00
50500505	STUD SHEAR CONNECTORS	EACH	10,088			10,088
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	315,710			315,710
50800515	BAR SPLICERS	EACH	360			360
50901735	BRIDGE FENCE RAILING (SIDEWALK)	FOOT	261			261
50901730	BRIDGE FENCE RAILING	FOOT	260			260
50901750	PARAPET RAILING	FOOT	261			261

* SPECIALTY ITEM

TYLIN INTERNATIONAL

USER NAME = #USERS#	DESIGNED - BES	REVISED -
	DRAWN - BES	REVISED -
PLDT SCALE = #SCALE#	CHECKED - JPM	REVISED -
PLDT DATE = 4/4/2012	DATE - 3/30/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

STUENKEL ROAD BRIDGE OVER I-57
SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 2 OF 5 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	99-1HB-R	WILL	63	5
CONTRACT NO. 60T40			ILLINOIS FED. AID PROJECT	

Rev.