

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN - 90 % FEDERAL, 10 % STATE		
				0004		0011
				STUENKEL ROAD	I-57	SN099-0526
51201800	FURNISHING STEEL PILES HP14X73	FOOT	6308			6308
51202305	DRIVING PILES	FOOT	6308			6308
51203800	TEST PILE STEEL HP14X73	EACH	3			3
51500100	NAME PLATES	EACH	1			1
52100520	ANCHOR BOLTS, 1"	EACH	52			52
52100540	ANCHOR BOLTS, 1 1/2"	EACH	52			52
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	70		70	
* 63100045	TRAFFIC BARRIER TERMINAL TYPE 2	EACH	2		2	
63200310	GUARDRAIL REMOVAL	FOOT	573	503	70	
64300450	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2	
66400305	CHAIN LINK FENCE, 6'	FOOT	415	415		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	11	11		
67100100	MOBILIZATION	L SUM	1	1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	14		14	

* SPECIALTY ITEM

* Specialty Items

Rev.

TYLIN INTERNATIONAL	USER NAME = *USER#	DESIGNED - BES	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	STUENKEL ROAD BRIDGE OVER I-57 SUMMARY OF QUANTITIES			F.A. RTE. 57	SECTION 99-1HB-R	COUNTY WILL	TOTAL SHEETS 63	SHEET NO. 6	
	PLOT SCALE = *SCALE#	CHECKED - JPM	REVISED -		SCALE: N.T.S.	SHEET NO. 3 OF 5 SHEETS	STA. TO STA.	CONTRACT NO. 60T40					
	PLOT DATE = 4/4/2012	DATE - 3/30/2012	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								