ROUTE	E: Sibley Blvd./147th St. (Cicero Ave. to Ha	alsted St.)				
CROSS	STREET	DIRECTION	LANE		PAVEMENT	REPAIR	REPAIF
FROM	ТО	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
FROIVI	10	. ,					
l la lata d		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT) 144	(SQ YD
Halsted		WB	2	12	12		16
	\/:	WB	2	12	12	144	16
	Vincennes	WB	2	12	30	360	40
Vincennes	Loomis	WB	2	6	12	72	8
Loomis		WB	2	6	12	72	8
		WB	2	6	12	72	8
		WB	2	6	12	72	8
		WB	2	12	12	144	16
	Wood	WB	2	6	50	300	33
Wood	Robey	WB	2	6	12	72	8
Robey		WB	2	12	25	300	33
		WB	2	12	12	144	16
		WB	2	12	20	240	27
	Dixie	WB	2	12	12	144	16
Cleveland		WB	2	6	20	120	13
		WB	2	6	200	1200	133
	Sacramento	WB	2	6	60	360	40
Sacramento	Kedzie	WB	2	6	60	360	40
Kedzie		WB	2	6	50	300	33
		WB	2	6	12	72	8
	Homan	WB	2	6	12	72	8
Homan		WB	2	6	250	1500	167
		WB	2	12	25	300	33
		WB	2	6	30	180	20
		WB	2	6	100	600	67
		WB	2	6	50	300	33
		WB	2	6	30	180	20
		WB	2	6	50	300	33
		WB	2	6	100	600	67
Homan	Railroad	WB	2	6	25	150	17
Railroad	Crawford	WB	2	6	12	72	8
Crawford		WB	2	6	12	72	8
		WB	2	6	12	72	8
		WB	2	6	20	120	13
		WB	2	6	50	300	33
	Kilbourn	WB	2	6	50	300	33
Kilbourn		WB	2	6	25	150	17
		WB	2	6	12	72	8
		WB	2	6	12	72	8
	Cicero	WB	2	6	12	72	8
Halsted		WB	1	6	12	72	8
		WB	1	6	12	72	8
	Loomis	WB	1	6	12	72	8
Loomis		WB	1	6	12	72	8
		WB	1	6	12	72	8
	Wood	WB	1	6	12	72	8
Wood	Robey	WB	1	6	12	72	8
Homan	Crawford	WB	1	6	12	72	8
Cicero		EB	2	6	12	72	8
0,0010		EB	2	6	50	300	33
		EB	2	6	12	72	8
		EB	2	6	12	72	8
						72	8
	Kilbourn	EB EB	2	6 6	12 12	72	8

ROUT	E: Sibley Blvd./147th St. ((Cicero Ave. to Ha	alsted St.)		(Continued)		
CROSS STREET		DIRECTION LANE		PAVEMENT	PAVEMENT	REPAIR	REPA
FROM	ТО	(EB/WB)	NO.	PATCH	PATCH	AREA	ARE
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ Y
Kilbourn		EB	2	6	100	600	67
		EB	2	6	50	300	33
	Keeler	EB	2	6	12	72	8
Keeler	Crawford	EB	2	6	50	300	33
Crawford		EB	2	12	12	144	16
		EB	2	6	12	72	8
		EB	2	6	12	72	8
		EB	2	12	50	600	67
		EB	2	10	12	120	13
		EB	2	6	50	300	33
		EB	2	6	100	600	67
		EB	2	6	300	1800	200
		EB	2	6	50	300	33
	Homan	EB	2	6	100	600	67
Homan	Kedzie	EB	2	12	50	600	67
Kedzie		EB	2	12	30	360	40
		EB	2	6	75	450	50
		EB	2	6	50	300	33
		EB	2	6	50	300	33
	Sacramento	EB	2	6	50	300	33
Sacramento		EB	2	6	12	72	8
		EB	2	6	12	72	8
		EB	2	6	75	450	50
		EB	2	6	12	72	8
	Harrison	EB	2	6	12	72	8
Harrison	Cleveland	EB	2	6	12	72	8
Cleveland	Dixie	EB	2	12	12	144	16
Dixie		EB	2	6	30	180	20
	Robey	EB	2	6	30	180	20
Robey	Wood	EB	2	6	12	72	8
Wood		EB	2	12	30	360	40
		EB	2	12	30	360	40
		EB	2	12	30	360	40
		EB	2	6	20	120	13
	Vincennes	EB	2	12	100	1200	133
Vincennes		EB	2	12	100	1200	133
	Halsted	EB	2	12	100	1200	133
Cicero	Kilbourn	EB	1	6	12	72	8
Sacramento	Harrison	EB	1	6	12	72	8
Harrison	Cleveland	EB	1	6	12	72	8
Dixie		EB	1	6	12	72	8
		EB	1	10	12	120	13
		EB	1	8	12	96	11
		EB	1	8	12	96	11
	Robey	EB	1	8	12	96	11
Robey	Wood	EB	1	6	12	72	8
Wood		EB	1	6	12	72	8
	Vincennes	EB	1	12	30	360	40
Vincennes		EB	1	6	12	72	8
	Halsted	EB	1	12	12	144	16
		TOTALS:			3760		302
					FT		S١

FILE NAME =	USER NAME = pencepl	DESIGNED -	REVISED -		PATCHING SCHEDULE					F.A RTF.	SECTION	COUNTY TOTAL SHEET
c:\pw_work\pwidot\pencepl\d0303732\D140	212-Design.dgn	DRAWN -	REVISED -	STATE OF ILLINOIS	SIBLEY BLVD./147TH ST.				VAR.	2012-018 RS	COOK & WILL 29 12	
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION							CONTRACT NO. 60T64	
	PLOT DATE = 4/5/2012			SCALE:	SHEET	OF	SHEET	S STA.	TO STA.		ILLINOIS FEE	AID PROJECT