ROUTE:	EB 79th St. (88th	Ave. to Cicero	Ave.)				
			,				
CROSS	STREET	DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIF
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WDTH	LENGTH	(SQ FT)	(SQ YD
88th Ave		EB	1	12	6	72	8
		EB	2	12	6	72	8
	87th	EB	2	12	6	72	8
87th		EB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	2	12	6	72	8
	86th	EB	2	12	6	72	8
86th	ootin	EB	1	12	6	72	8
0011		EB	1	12	6	72	8
	85th	EB	2	12	6	72	8
85th	0000	EB	<u> </u>	12	6	72	8
00111							
		EB	2	12	6	72	8
	0.41	EB	2	12	6	72	8
0.411	84th	EB	2	12	6	72	8
84th		EB	1	12	6	72	8
	83rd	EB	2	12	6	72	8
83rd		EB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	2	12	6	72	8
		EB	2	12	6	72	8
	81st	EB	2	12	6	72	8
81st		EB	2	13	6	78	9
	Roberts	EB	LTL	11	6	66	7
Roberts		EB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	2	12	6	72	8
		EB	2	12	6	72	8
		EB	2	12	6	72	8
		EB	2	12	6	72	8
	78th Ave	EB	2	12	6	72	8
7041- 4	7 oth Ave						
78th Ave		EB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	2	12	6	72	8
		EB	2	12	6	72	8
		EB	2	12	6	72	8
		EB	2	12	6	72	8
	Oketo	EB	2	12	6	72	8
Oketo		EB	1	12	6	72	8
		EB	1	12	6	72	8
	Harlem	EB	1	12	6	72	8
Harlem		EB	1	12	6	72	8
		EB	2	12	6	72	8
	Neva	EB	3	12	6	72	8
Neva	Nottingham	EB	1	12	6	72	8
	Nottingfiaffi	EB	1	12	6	72	8
Nottingham							
	<u> </u>	EB	2	12	6	72	8
Newland	Sayre	EB EB	2 2	12 12	6 6	72 72	8 8
	1		2	10		70	

ROUTE:	EB 79th St. (88th	Ave. to Cicero	o Ave.)	(Continued)			
CDOSS	STREET	DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM		(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
FROM	ТО	. ,			LENGTH		
		(NB/SB)	(1, 2, 3)	WDTH		(SQ FT)	(SQ YD
New England		EB	1	12	6	72	8
	Newcastle	EB	2	12	6	72	8
Newcastle		EB	1	12	6	72	8
	Oak Park	EB	2	12	6	72	8
Oak Park		EB	1	12	6	72	8
	Rutherford	EB	2	12	6	72	8
Rutherford	Normandy	EB	2	12	6	72	8
Normandy	,	EB	1	12	6	72	8
	Natoma Ave	EB	2	12	6	72	8
Natoma Ave	Nashville	EB	2	12	6	72	8
Nashville	Neenah	EB	1	12	6	72	8
					-		-
Neenah	Natchez	EB	1	12	6	72	8
Natchez	Narragansett	EB	1	12	6	72	8
Narragansett		EB	1	12	6	72	8
	Mulligan Ave	EB	2	12	6	72	8
Mulligan Ave	Mobile	EB	2	12	6	72	8
Mobile		EB	1	12	6	72	8
		EB	1	12	6	72	8
	Melvina	EB	1	12	6	72	8
McVickey	Austin	EB	2	12	6	72	8
Austin	Austin	EB	1	12	6	72	8
Austin							_
		EB	1	12	6	72	8
		EB	2	12	6	72	8
	Mayfield	EB	2	12	6	72	8
Massasoit		EB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	1	12	6	72	8
	Major	EB	2	12	6	72	8
Parkside Ave	Central	EB	2	12	6	72	8
Central	Luna	EB	 1,2,LTL	36	6	216	24
Linder	State	EB	1,2,212	24	6	144	16
	Sidle			12		72	8
State		EB	1		6		-
		EB	1	12	6	72	8
	Lorel	EB	2	12	6	72	8
Lorel		EB	1	12	6	72	8
	Lockwood	EB	2	12	6	72	8
Lockwood		EB	1	12	6	72	8
		EB	2	12	6	72	8
	Latrobe	EB	2	12	6	72	8
Latrobe		EB	1	12	6	72	8
Latiobe		EB	1	12	6	72	8
		EB	1	12	6	72	8
	LeClaire	EB	2	12	6	72	8
LeClaire		EB	1	12	6	72	8
	Lawler	EB	2	12	6	72	8
Lawler		EB	1	12	6	72	8
	Lavergne	EB	2	12	6	72	8
Lavergne	ŭ	EB	1	12	6	72	8
	Laporte	EB	1	12	6	72	8
lanorto	Lapone	EB	1	12	6	72	8
Laporte							
		EB	1	12	6	72	8
		EB	RTL	12	6	72	8
	Cicero	EB	LTL	12	6	72	8
		TOTALS:			660		904
					FT		SY

FILE NAME =	USER NAME = pencepl	DESIGNED -	REVISED -		PATCHING SCHEDULE				F.A	SECTION	COUNTY TOTAL SHEET
c:\pw_work\pwidot\pencepl\d0303732\D140	12-Design.dgn	DRAWN -	REVISED -	STATE OF ILLINOIS				VAR.	2012-018 RS	COOK & WILL 29 18	
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION	79TH ST.						CONTRACT NO. 60T64
	PLOT DATE = 4/5/2012 DATE - REVISED -	REVISED -		SCALE:	SHEET	OF	SHEETS STA.	TO STA.			AID PROJECT