

VARIOUS COUNTIES

SUMMARY OF QUANTITIES

CODE	ITEM DESCRIPTION	UNIT	TOTAL QTY.	CONST. TYPE	CONST. TYPE	CONST. TYPE	CONST. TYPE	CONST. TYPE	CONST. TYPE	CONST. TYPE
				CODE 0021 (100% STATE BROADBAND FIBER PROGRAM FUNDS) RURAL	CODE 0021 (100% STATE BROADBAND FIBER PROGRAM FUNDS) URBAN	CODE 0021 (100% STATE BROADBAND FIBER PROGRAM FUNDS) RURAL	CODE 0021 (100% STATE BROADBAND FIBER PROGRAM FUNDS) URBAN	CODE 0021 (100% STATE BROADBAND FIBER PROGRAM FUNDS) RURAL	CODE 0021 (100% STATE BROADBAND FIBER PROGRAM FUNDS) URBAN	CODE 0021 (100% STATE BROADBAND FIBER PROGRAM FUNDS) RURAL
67100100	MOBILIZATION	L SUM	1.0	0.03	0.19	0.17	0.03	0.12	0.07	0.39
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1.0							1.0
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1.0			1.0				
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1.0				1.0			
81100800	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., GALVANIZED STEEL	FOOT	240.0				240.0			
81300948	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 24" X 24" X 10"	EACH	2.0				2.0			
X8710035	FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	386267.0	11075.0	73539.0	64141.0	12117.0	47924.0	27057.0	150414.0
Z0033052	COMMUNICATIONS VAULT	EACH	100.0	3.0	21.0	15.0	5.0	12.0	7.0	37.0
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1.0		0.5			0.2		0.3
X8101100	UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	381247.0	10925.0	72489.0	63391.0	11847.0	47324.0	26707.0	148564.0

R R R R R

FILE NAME =	USER NAME = keithbr	DESIGNED -	REVISED -
ct:\notes\series plans\68803 - D4 Fiber Project Sheets 1-109 (MeComb to Monmouth) - Final		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2012	VARIOUS	220	3
			CONTRACT NO. 68803	
[ILLINOIS] FED. AID PROJECT				