



SPRING LAKE RD.

N 1500th RD.

E 1200th St

UNDRGRD C MD  
136 FT. (PUSHED)  
UNDER ROADWAY

UNDRGRD C MD  
744 FT.

UNDRGRD C MD  
88 FT. (PUSHED)  
UNDER DRAINAGE STRUCTURE

UNDRGRD C MD  
632 FT.

© 2011 Google  
Image McDonough County GIS Consortium

Google earth

40°29'49.19" N 90°40'28.97" W elev 709 ft

Eye alt 2794 ft

SCHEDULE OF QUANTITIES		
ITS FIBER (US 67 FROM MACOMB TO MONMOUTH) - SHEET 6		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	1600.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	1600.0

FILE NAME =	USER NAME = keathbr	DESIGNED -	REVISED -
ct:\notes\erics plans\68803 - D4 Fiber Project Sheets 1-109 (Macomb to Monmouth) - Final		DRAWN -	REVISED -
	PLOT SCALE = 171.6216 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 4/23/2012	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

FIBER OPTIC CONDUIT AND CABLE PROJECT  
US 67 (FROM MACOMB TO MONMOUTH) CONTINUED  
SCALE: SHEET NO. 6 OF 106 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2012	VARIOUS	220	9
CONTRACT NO. 68B03			ILLINOIS FED. AID PROJECT	