



UNDRGRD C MD
665 FT.

UNDRGRD C MD
68 FT. (PUSHED)
UNDER DRAINAGE STRUCTURE

UNDRGRD C MD
378 FT.

COMMUNICATIONS VAULT
1.0 EACH

UNDRGRD C MD
482 FT.

SCHEDULE OF QUANTITIES		
ITS FIBER (US 67 FROM MACOMB TO MONMOUTH) - SHEET 7		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	1593.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	1643.0
COMMUNICATIONS VAULT	EACH	1.0

© 2011 Google
Image McDonough County GIS Consortium

Google earth

Imagery Date: 3/31/2010 1998

40°30'04.65" N 90°40'27.88" W elev 700 ft

Eye alt 2794 ft

FILE NAME =

USER NAME = keithbr	DESIGNED -	REVISED -
PROJECT SHEETS 1-109 (Macomb to Monmouth) - Final.DRAWN2.dgn	CHECKED -	REVISED -
PLOT SCALE = 171.6216' / in.	DATE -	REVISED -
PLOT DATE = 4/23/2012		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FIBER OPTIC CONDUIT AND CABLE PROJECT
US 67 (FROM MACOMB TO MONMOUTH) CONTINUED

SCALE: SHEET NO. 7 OF 106 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2012	VARIOUS	220	10
			CONTRACT NO. 68B03	
ILLINOIS FED. AID PROJECT				