



COMMUNICATIONS VAULT  
1.0 EACH

UNDRGRD C MD  
227 FT.

UNDRGRD C MD  
2092 FT.



SCHEDULE OF QUANTITIES		
ITS FIBER (US 34 FROM MONMOUTH TO GALESBURG) - SHEET 24		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	2319.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	2369.0
COMMUNICATIONS VAULT	EACH	1.0

© 2011 Google

Image USDA Farm Service Agency

Google earth

Imagery Date: 6/27/2009 1998

40°54'58.54" N 90°28'36.57" W elev 766 ft

Eye alt 2793 ft

FILE NAME =	USER NAME = keathbr	DESIGNED -	REVISED -
ct:\notes\erics plans\68B03 - D4 Fiber Project Sheets 110-157 (Monmouth to Galesburg)	DRAWN 19-12.dgn	CHECKED -	REVISED -
	PLOT SCALE = 164.7568' / in.	DATE -	REVISED -
	PLOT DATE = 4/23/2012		

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

FIBER OPTIC CONDUIT AND CABLE PROJECT  
US 34 (FROM MONMOUTH TO GALESBURG) CONTINUED

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2012	VARIOUS	220	133
CONTRACT NO. 68B03				
ILLINOIS FED. AID PROJECT				

SCALE: SHEET NO. 24 OF 48 SHEETS STA. TO STA.