



Knox Hwy 35

KNOX HWY 35

KNOX HWY 35

UNDRGRD C MD

85 FT.

UNDRGRD C MD

106 FT. (PUSHED)

UNDRGRD C MD

736 FT.

COMMUNICATIONS VAULT

1.0 EACH

UNDRGRD C MD

632 FT.



© 2011 Google  
Image © 2011 GeoEye

Google earth

Imagery Date: 9/12/2011 1998

41°04'35.77" N 90°20'03.82" W elev 762 ft

Eye alt 2791 ft

SCHEDULE OF QUANTITIES		
ITS FIBER (GALESBURG TO WOODHULL) - SHEET 24		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	1559.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	1609.0
COMMUNICATIONS VAULT	EACH	1.0

FILE NAME =	USER NAME = keathbr	DESIGNED -	REVISED -
ct:\notes\erics plans\68803 - D4 Fiber Project Sheets 158-206 (Galesburg to Woodhull) -	FDRAWN 9-12.dgn	CHECKED -	REVISED -
	PLOT SCALE = 163.0405' / in.	DATE -	REVISED -
	PLOT DATE = 4/24/2012		

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

FIBER OPTIC CONDUIT AND CABLE PROJECT  
I-74 (FROM GALESBURG TO WOODHULL) CONTINUED  
SCALE: SHEET NO. 24 OF 49 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2012	VARIOUS	220	181
ILLINOIS FED. AID PROJECT			CONTRACT NO. 68B03	