



COMMUNICATIONS VAULT
1.0 EACH

UNDRGRD C MD
163 FT.

UNDRGRD C MD
2502 FT.

KNOX RD. 650E

SCHEDULE OF QUANTITIES		
ITS FIBER (GALESBURG TO KNOXVILLE) - SHEET 12		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	2665.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	2715.0
COMMUNICATIONS VAULT	EACH	1.0

Imagery Date: 9/14/2011

© 2012 Google
Image USDA Farm Service Agency

40°55'42.23" N 90°18'48.39" W elev 731 ft

Google earth

Eye alt 2794 ft

FILE NAME =	USER NAME = keithbr	DESIGNED -	REVISED -
ct:\notes\erics plans\68B03 - D4 Fiber Project Sheets 207-220 (Galesburg to Knoxville)	DRAWN-21-12.dgn	CHECKED -	REVISED -
	PLOT SCALE = 182.6054' / in.	DATE -	REVISED -
	PLOT DATE = 4/24/2012		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FIBER OPTIC CONDUIT AND CABLE PROJECT
I-74 (FROM GALESBURG TO KNOXVILLE) CONTINUED

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2012	VARIOUS	220	218
CONTRACT NO. 68B03			ILLINOIS FED. AID PROJECT	

SCALE: SHEET NO. 12 OF 14 SHEETS STA. TO STA.