



ASBESTOS CONTAINING MATERIAL TO REMOVED - PARCEL # 6148114 (BUILDING NO. 1)						
MATERIAL NO.	MATERIAL DESCRIPTION	LOCATION	FRIABLE	ASBESTOS TYPE	ASBESTOS %	QUANTITY (SQ FT)
2	TRANSITE PANELS AND FELT BACKING	DORMER COVERS ON ROOFS	NO	CHRYSOTILE	TRANSITE 15%	110 SF
5	TRANSITE PANELS	BUILDING C, UTILITY ROOM	NO	CHRYSOTILE	25%	3,535 SF
6	9" X 9" GRAY WITH SPOTS VINYL FLOOR	BUILDING A, CLOSET	NO	CHRYSOTILE	TILE 4%	4 SF
7	9" X 9" TAN WITH BROWN/WHITE STREAKS VINYL FLOOR TILE/MASTIC	ROOMS 11, 12, 14, 15, 32	NO	CHRYSOTILE	TILE 4%	605 SF
8	9" X 9" GREEN WITH WHITE STREAKS VINYL FLOOR TILE/MASTIC	ROOMS 16, 17, 25, 26, 28, 30	NO	CHRYSOTILE	TILE 7%	580 SF
9	9" X 9" DARK BROWN WITH WHITE/ORANGE STREAKS VINYL FLOOR	ROOMS 18, 19, 20, 22, 23, 24	NO	CHRYSOTILE	TILE 5%	725 SF
11	9" X 9" GRAY/BLACK AND WHITE STREAKS VINYL FLOOR TILE/MASTIC	ROOMS 27, 28, 29, 30	NO	CHRYSOTILE	TILE 6%	360 SF
12	9" X 9" RED/YELLOW WITH TAN STREAKS VINYL FLOOR TILE/MASTIC	ROOM 31	NO	CHRYSOTILE	TILE 5%	60 SF
13	9" X 9" TAN WITH YELLOW AND RED STREAKS VINYL FLOOR TILE/MASTIC	ROOM 31	NO	CHRYSOTILE	TILE 5%	60 SF
14	9" X 9" TAN WITH BLACK STREAKS VINYL FLOOR TILE	ROOM 32	NO	CHRYSOTILE	TILE 7%	60 SF
15	9" X 9" BLUE WITH TAN STREAKS VINYL FLOOR TILE	ROOM 32	NO	CHRYSOTILE	TILE 6%	60 SF
18	9" X 9" TAN WITH BROWN STREAKS VINYL FLOOR TILE/MASTIC	ROOMS 23, 24	NO	CHRYSOTILE	TILE 6%	2,410 SF
19	9" X 9" TAN WITH BROWN AND TAN STREAKS VINYL FLOOR TILE/MASTIC	ROOMS 18, 19, 20	NO	CHRYSOTILE	TILE 6%	360 SF

ASBESTOS CONTAINING MATERIAL TO REMOVED - PARCEL # 6148114 (BUILDING NO. 2)						
MATERIAL NO.	MATERIAL DESCRIPTION	LOCATION	FRIABLE	ASBESTOS TYPE	ASBESTOS %	QUANTITY (SQ FT)
1	MULTI-LAYER ROOFING	FLAT ROOF, ROOF OVER STAIRS TO	NO	CHRYSOTILE	12%	220 SF
3	TRANSITE VENT TYPE	ROOF THROUGH BASEMENT	NO	CHRYSOTILE, CROCIDOLITE	20%, 5%	20 LF
4	TRANSITE SHINGLES	EXTERIOR	NO	CHRYSOTILE	20%	1,500 SF
6	WINDOW CAULKING	BASEMENT WINDOWS	NO	CHRYSOTILE	< 1%	65 LF
7	12" X 12" BEIGE WITH TAN SPLOTCHES VINYL FLOOR TILE/MASTIC	BASEMENT	NO	CHRYSOTILE	TILE 3%	215 SF
8	DUCT SEAL TAPE	BASEMENT RETURNS PLENUMS	YES	CHRYSOTILE	50%	25 LF
13	WINDOW CAULKING	HOUSE WINDOWS	NO	CHRYSOTILE	2%	200 LF
20	GREEN & BROWN VINYL SHEET FLOORING	HALLWAY 1 AT NORTH ENTRANCE	NO	CHRYSOTILE	20%	10 SF
21	12" X 12" BEIGE WITH TAN & WHITE SPLOTCHES VINYL FLOOR TILE/MASTIC	BATH SUBFLOOR	NO	CHRYSOTILE	TILE 3%	35 SF

