

90% FED.  
10% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0005 RURAL	0005 URBAN				
67100100	MOBILIZATION	L SUM	1	1	0				
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	8	4	4				
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1	0				
70300100	SHORT TERM PAVEMENT MARKING	FOOT	32,794	30,931	1,863				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	429102	404942	24160				
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	625	305	320				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	154,382	145,488	8,894				
X 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	380806	359365	21441				
X 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	625	305	320				
X 78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	48296	45577	2719				
X 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4870	4554	316				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	4870	4554	316				
+ Z0076600	TRAINEES	HOUR	5000	2,500	2,500				
Z0034105	MATERIAL TRANSFER DEVICE	TON	57,698	54,200	3,498				

X SPECIALTY ITEM

+ 0042

FILE NAME =  
c:\pwwork\pwwid\chil\0301187\d876798-d  
USER NAME = chilsl  
t:\plan.dgn  
PLOT SCALE = 100.0000 1/16"  
PLOT DATE = 3/22/2012

DESIGNED - GEL  
DRAWN - LAC  
CHECKED - MDP  
DATE - 3/20/2012  
REVISED -  
REVISED -  
REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 2 OF 2 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	61-(2,3,3-1,4,5,5-1,6) RS-2	MARION	8	4
CONTRACT NO. 76F90				

ILLINOIS FED. AID PROJECT