



| CODE NO. | ITEM                                     | UNIT  | CONSTRUCTION CODE |                |
|----------|--|-------|-------------------|----------------|
|          |  |       | HBP FUNDS         | TOTAL QUANTITY |
| 48203029 | HOT-MIX ASPHALT SHOULDERS, 8"            | SQ YD | 80% FED           | 671            |
| 48203037 | HOT-MIX ASPHALT SHOULDERS, 10"           | SQ YD | 20% STATE         | 712            |
| 50100100 | REMOVAL OF EXISTING STRUCTURES           | EACH  | BRIDGE            | 1              |
| 50157300 | PROTECTIVE SHIELD                        | SQ YD | 0011              | 167            |
| 50200100 | STRUCTURE EXCAVATION                     | CU YD | RURAL             | 224            |
| 50300100 | FLOOR DRAINS                             | EACH  |                   | 2              |
| 50300225 | CONCRETE STRUCTURES                      | CU YD |                   | 166.5          |
| 50300255 | CONCRETE SUPERSTRUCTURE                  | CU YD |                   | 321.5          |
| 50300260 | BRIDGE DECK GROOVING                     | SQ YD |                   | 785            |
| 50300280 | CONCRETE ENCASEMENT                      | CU YD |                   | 4.8            |
| 50300300 | PROTECTIVE COAT                          | SQ YD |                   | 1004           |
| 50500105 | FURNISHING AND ERECTING STRUCTURAL STEEL | L SUM |                   | 1              |
| 50500505 | STUD SHEAR CONNECTORS                    | EACH  |                   | 4515           |
| 50800105 | REINFORCEMENT BARS                       | POUND |                   | 17970          |

| CODE NO.            | ITEM                             | UNIT             | CONSTRUCTION CODE |                 |
|---------------------|----------------------------------|------------------|-------------------|-----------------|
|                     |                                  |                  | HBP FUNDS         | TOTAL QUANTITY  |
| 50800205            | REINFORCEMENT BARS, EPOXY COATED | POUND            | 80% FED           | 102760          |
| 50800515            | BAR SPLICERS                     | EACH             | 20% STATE         | 904             |
| 50800530            | MECHANICAL SPLICERS              | EACH             | BRIDGE            | 96              |
| 51100100            | SLOPE WALL 4 INCH                | SQ YD            | 0011              | 458             |
| 51201610            | FURNISHING STEEL PILES HP12X63   | FOOT             | RURAL             | 414             |
| 51202305            | DRIVING PILES                    | FOOT             |                   | 414             |
| 51203610            | TEST PILE STEEL HP12X63          | EACH             |                   | 2               |
| 51500100            | NAME PLATES                      | EACH             |                   | 1               |
| X 51603000          | DRILLED SHAFT IN SOIL            | CU YD            |                   | 24              |
| X 51604000          | DRILLED SHAFT IN ROCK            | CU YD            |                   | 16              |
| 52100520            | ANCHOR BOLTS, 1"                 | EACH             |                   | 28              |
| 52100530            | ANCHOR BOLTS, 1 1/4"             | EACH             |                   | 28              |
| 54213447            | END SECTIONS 12"                 | EACH             |                   | 3               |
| <del>58700300</del> | <del>CONCRETE SEALER</del>       | <del>SQ FT</del> |                   | <del>1182</del> |

X SPECIALTY ITEM

|          |  |
|----------|--|
| LAYOUT   |  |
| DRAWN    |  |
| REVIEWED |  |

|  |                        |                 |           |
|--|------------------------|-----------------|-----------|
| FILE NAME =                              | USER NAME = brenn00248 | DESIGNED - BKC  | REVISED - |
| at\work\ing\dms23839\0978134-shr-S00.dgn |                        | DRAWN - BKC     | REVISED - |
| MODEL = S00.PAGE 2                       |                        | CHECKED - MH    | REVISED - |
|  |                        | DATE - 02/23/12 | REVISED - |

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

IL-145 (OVER IL-146)  
SUMMARY OF QUANTITIES

SCALE: SHEET NO. 2 OF 4 SHEETS STA. TO STA.

|                     |         |        |                           |           |
|---------------------|---------|--------|---------------------------|-----------|
| F.A.P. RTE.         | SECTION | COUNTY | TOTAL SHEETS              | SHEET NO. |
| 132                 | 103B-1  | POPE   | 52                        | 4         |
| FED. ROAD DIST. NO. |         |        | ILLINOIS FED. AID PROJECT |           |
|                     |         |        | CONTRACT NO. 78134        |           |