



CONSTRUCTION CODE
HBP FUNDS
80% FED
20% STATE
BRIDGE
0011
RURAL

CONSTRUCTION CODE
HBP FUNDS
80% FED
20% STATE
BRIDGE
0011
RURAL

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	64
60100945	PIPE DRAINS 12"	FOOT	204
60500060	REMOVING INLETS	EACH	4
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	7.4
60600605	CONCRETE CURB, TYPE B	FOOT	30
60900515	CONCRETE THRUST BLOCKS	EACH	3
X 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	925.0
X 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4
X 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4
63200310	GUARDRAIL REMOVAL	FOOT	1106
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	6
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70106700	TEMPORARY RUMBLE STRIP	EACH	12
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	3
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	171
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	10884
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	3689
70400100	TEMPORARY CONCRETE BARRIER	FOOT	962.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	962.5
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	2
72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	1
X 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6297

X SPECIALTY ITEM

LAYOUT	
DRAWN	
REVIEWED	

FILE NAME : e:\working\dm23838\0978134-sht-500.dgn	USER NAME : brann00248	DESIGNED - BKC	REVISED -
MODEL = 500.PAGE 3	PLOT SCALE = 2.0000' / in.	DRAWN - BKC	REVISED -
	PLOT DATE = 02/23/2012	CHECKED - MH	REVISED -
		DATE - 02/23/12	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**IL-145 (OVER IL-146)  
SUMMARY OF QUANTITIES**

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
132	103B-1	POPE	52	5
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 78134	

SCALE: SHEET NO. 3 OF 4 SHEETS STA. TO STA.