

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				80% FED.	80% STATE	50% STATE			
				20% STATE	20% TOWN	50% TOWN	100% TOWN	100% STATE	
				004	004	004	004	004	
* 25200100	SODDING	SQ YD	11233	11233					
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	72	72					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	325	325					
28000305	TEMPORARY DITCH CHECKS	FOOT	210	210					
28000400	PERIMETER EROSION BARRIER	FOOT	784	784					
28000500	INLET AND PIPE PROTECTION	EACH	151	151					
28001000	AGGREGATE ( EROSION CONTROL )	TON	106	106					
28100207	STONE RIPRAP, CLASS A4	TON	221	221					
28100225	STONE RIPRAP, CLASS B3	TON	63	63					
28200200	FILTER FABRIC	SQ YD	521	521					
28500100	FABRIC FORMED CONCRETE REVETMENT MATS	SQ YD	103	103					
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	14350	14350					
35501310	HOT - MIX ASPHALT BASE COURSE, 6 1/2"	SQ YD	484	484					
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	300	300					

\*SPECIALTY ITEM

FILE NAME =  
schedule.sheets.dgn

USER NAME = boyernj

DESIGNED -

REVISED -

DRAWN -

REVISED -

PLOT SCALE = 100.0000' / 1"

CHECKED -

REVISED -

PLOT DATE = 3/20/2012

DATE -

REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	16W-1, RS-3	FULTON	347	14
			CONTRACT NO. 88795	

ILLINOIS FED. AID PROJECT