



SIDEROAD TYPICAL SECTION

PROPOSED

- ① COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24
- ② SUB-BASE GRANULAR MATERIAL, TYPE B (8")
- ③ PORTLAND CEMENT CONCRETE PAVEMENT 8-3/4" (JOINTED)
- ④ GEOTECHNICAL FABRIC FOR GROUND STABILIZATION

FILE NAME = miscsheets.dgn	USER NAME = dclckhausen	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SIDEROAD TYPICAL SECTION</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -					317	16W-1, RS-3	FULTON	347	28
PLOT DATE = 3/12/2012	DATE -	REVISED -	SCALE:		SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT		
									<b>CONTRACT NO. 88795</b>			