

TEMPORARY PAVEMENT				
EASTBOUND (SOUTHSIDE)				
STA TO STA	OFFSET	WIDTH (ft)	AREA (SY)	STAGE/NOTES
19+50 to 20+50	LT	5	55.6	STAGE 1A
20+50	LT	5		
20+50 to 23+00	LT	5	83.3	STAGE 1A
23+00	LT	1		
879+72 to 882+22	LT	1	83.3	STAGE 3A
882+22	LT	5		
882+22 to 883+22	LT	5	55.6	STAGE 3A
883+22	LT	5		
883+22 to 885+04	LT	2	40.4	STAGE 3A -Placed outside of new PCC pavement built in stage 3A -- (See Note 1)
885+04	LT	2		
924+69 to 924+85	LT	0	8.9	STAGE 3A - Temporary Pavement in the area of the proposed curb "Bump Out"
924+85	LT	10		
924+85 to 925+07	LT	10	24.4	STAGE 3A - Temporary Pavement in the area of the proposed curb "Bump Out"
925+07	LT	10		
927+13.5 to 927+52	LT	10	42.8	STAGE 3A - Temporary Pavement in the area of the proposed curb "Bump Out"
927+52	LT	10		
927+52 to 927+70	LT	10	10.0	STAGE 3A - Temporary Pavement in the area of the proposed curb "Bump Out"
927+70	LT	0		
0+29 to 0+49	LT	0	11.1	STAGE 3A - Temporary Pavement in the area of the proposed curb "Bump Out"
0+49	LT	10		
0+49 to 0+70.5	LT	10	23.9	STAGE 3A - Temporary Pavement in the area of the proposed curb "Bump Out"
0+70.5	LT	10		
2+92.5 to 3+14	LT	10	23.9	STAGE 3A - Temporary Pavement in the area of the proposed curb "Bump Out"
3+14	LT	10		
3+14 to 3+32	LT	10	10.0	STAGE 3A - Temporary Pavement in the area of the proposed curb "Bump Out"
3+32	LT	0		
EASTBOUND SUBTOTAL			473.2	

TEMPORARY PAVEMENT				
WESTBOUND (NORTHSIDE)				
STA TO STA	OFFSET	WIDTH (ft)	AREA (SY)	STAGE/NOTES
3+65 to 3+96	RT	5	12.1	PRE-STAGE 1
3+96	RT	2		
17+38 to 19+50	RT	3	70.7	PRE-STAGE 1
19+50	RT	3		
19+50 to 20+50	RT	5	55.6	PRE-STAGE 1
20+50	RT	5		
20+50 to 23+00	RT	5	83.3	PRE-STAGE 1
23+00	RT	1		
879+72 to 882+22	RT	1	83.3	PRE-STAGE 3
882+22	RT	5		
882+22 to 883+22	RT	5	55.6	PRE-STAGE 3
883+22	RT	5		
883+22 to 891+00	RT	3	259.3	PRE-STAGE 3
891+00	RT	3		
883+22 to 885+04	RT	2	40.4	STAGE 3B -Placed outside of new PCC pavement built in stage 3B -- (See Note 1)
885+04	RT	2		
924+70 to 924+85	RT	0	8.3	STAGE 3B - Temporary Pavement in the area of the proposed curb "Bump Out"
924+85	RT	10		
924+85 to 925+07	RT	10	24.4	STAGE 3B - Temporary Pavement in the area of the proposed curb "Bump Out"
925+07	RT	10		
927+17 to 927+52	RT	10	38.9	STAGE 3B - Temporary Pavement in the area of the proposed curb "Bump Out"
927+52	RT	10		
927+52 to 927+75	RT	10	12.8	STAGE 3B - Temporary Pavement in the area of the proposed curb "Bump Out"
927+75	RT	0		
WESTBOUND SUBTOTAL			745	
EASTBOUND SUBTOTAL			473	
TOTAL			1218	

NOTES:

- Gutter Outlets and curb transitions from Sta. 884+58 to Sta. 885+04 left and right shall be constructed during Stage 4.
- All lane shift tapers are 50:1.
- Temporary pavement length includes taper length and 100' tangent prior to work zone.

FILE NAME = schedule_sheets.dgn	USER NAME = harstkj	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.P. RTE. 317	SECTION 16W-1, RS-3	COUNTY FULTON	TOTAL SHEETS 347	SHEET NO. 44	CONTRACT NO. 88795 ILLINOIS FED. AID PROJECT	
	PLOT SCALE = 100.0000' / 1" =	CHECKED - DATE -	REVISED - REVISED -			SCALE:	SHEET OF SHEETS	STA.	TO STA.			
	PLOT DATE = 3/21/2012											