



ELEVATIONS

- ① 713.97
- ② 713.82
- ③ 713.38
- ④ 713.37
- ⑤ 712.93
- ⑥ 712.92
- ⑦ 712.48

NOTES:

1. SEE HANDRAIL DETAILS FOR INFORMATION PERTAINING TO THE INSTALLATION OF PIPE HANDRAILS.
2. WHERE HANDRAIL IS BEING INSTALLED IN THE BACK OF THE SIDEWALK, THE BACK 1' OF THE SIDEWALK SHALL BE CONSTRUCTED 6" THICK TO ALLOW FOR FASTENING OF THE HANDRAIL TO THE SIDEWALK.
3. NOSINGS OF STEPS SHALL HAVE 1/2" RADIUS (MAX).

SECTION DD

(STA. 924+92 TO STA. 924+99 RT)

6x6 W1.4 STEEL WIRE MESH

NO. 4 X 18 TIE BARS AT 12" CTS. (STA. 924+92 TO STA. 924+99 RT)

FILE NAME = miscsheets.dgn	USER NAME = horstkj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SIDEWALK DETAILS WALNUT ST. TO PEARL ST.			F.A.P. RTE. = 317	SECTION = 16W-1, RS-3	COUNTY = FULTON	TOTAL SHEETS = 347	SHEET NO. = 160
	PLOT SCALE = 20,000' / in.	DRAWN -	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT				
	PLOT DATE = 3/21/2012	CHECKED -	REVISED -		CONTRACT NO. 88795							