



- ① WHITE THERMOPLASTIC STOP BAR PAVEMENT MARKING LINE - 24" SOLID
- ② WHITE THERMOPLASTIC PAVEMENT MARKING LINE - 8" SOLID
- ③ YELLOW THERMOPLASTIC PAVEMENT MARKING LINE - 12" (ON 45° ANGLE, 20' CTC)
- ④ WHITE THERMOPLASTIC MARKING LINE - 10' LONG, 30' GAP - 4"
- ⑤ THERMOPLASTIC PAVEMENT MARKING, LETTERS AND SYMBOLS (FOR LEFT AND RIGHT TURN LANE ONE ARROW 20' FROM FRONT OF STORAGE AND ONE ARROW 20' AT BACK OF STORAGE)
- ⑥ WHITE THERMOPLASTIC PAVEMENT MARKING LINE - 8" (2' LONG, 6' GAP)
- ⑦ WHITE THERMOPLASTIC PAVEMENT MARKING LINE - 8" (3' LONG, 9' GAP)
- ⑧ DOUBLE YELLOW THERMOPLASTIC PAVEMENT MARKING LINE - 4" SOLID
- ⑨ YELLOW THERMOPLASTIC PAVEMENT MARKING LINE - 4" SOLID
- ⑩ WHITE PAINT PAVEMENT MARKING LINE - 8" SOLID
- ⑪ WHITE PAINT PAVEMENT MARKING LINE - 8" (2' LONG, 6' GAP)
- ⑫ PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS (FOR LEFT AND RIGHT TURN LANE ONE ARROW 20' FROM FRONT OF STORAGE AND ONE ARROW 20' AT BACK OF STORAGE)
- ⑬ WHITE THERMOPLASTIC PAVEMENT MARKING LINE - 6" SOLID



FILE NAME = I:\09\Jobs\09L\0027A\CADD\Road\Sheet\0-102.mxd	USER NAME = davis00878	DESIGNED - DLC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	NORTHMOOR ROAD STAGE 2 IMPROVEMENT PAVEMENT MARKING PLAN		F.A.U. RTE. = 6647	SECTION = 05-00302-01-PV	COUNTY = PEORIA	TOTAL SHEETS = 125	SHEET NO. = 47
	PLOT SCALE = 40,0000' / in.	CHECKED - MGD	REVISED -				SCALE: 1"=20'	SHEET NO. OF SHEETS	STA. 71+00.00 TO STA. 77+00.00	FED. ROAD DIST. NO. = 11-00047-03-PV	ILLINOIS FED. AID PROJECT
PLOT DATE = 04\02\2012	DATE = 03/27/12	REVISED -	REVISED -								