

PAVING SCHEDULE	PROCESSING MODIFIED SOILS 12"	LIME	SUB-BASE GRANULAR MATERIAL, TYPE C	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	HOT-MIX ASPHALT BASE COURSE WIDENING, 6"	HOT-MIX ASPHALT BASE COURSE WIDENING, 8"	AGGREGATE SURFACE COURSE, TYPE B (8")	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	HMA PAVEMENT (FULL-DEPTH), 8"	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	WHITEWASHING FOR CONCRETE PAVEMENT	AGGREGATE SHOULDERS, TYPE B 8"	HOT-MIX ASPHALT SHOULDERS 6"	HOT-MIX ASPHALT SHOULDERS 8"	PORTLAND CEMENT CONCRETE SHOULDERS 8"
LOCATION	SQ YD	TON	CU YD	SQ YD	SQ YD	SQ YD	TON	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD
BROADWAY ROAD																
STA. 82+86.96 TO STA. 91+67.30						206.0		0.09	23.0				41.0		511.0	
VETERANS DRIVE																
STA. 99+76.97 TO STA. 112+00.00	11,033.0	260.7	374.0	9,039.0							8,617.0	8,617.0	479.0			2,252.0
STA. 112+00.00 TO STA. 124+00.00	10,534.0	248.9	356.0	8,667.0							8,267.0	8,267.0	303.0			2,134.0
STA. 124+00.00 TO STA. 136+00.00	10,534.0	248.9	356.0	8,667.0							8,267.0	8,267.0	521.0			2,134.0
STA. 126+00.00 RT							107.9									
STA. 136+00.00 TO STA. 140+26.30	4,219.0	99.7	142.0	3,277.0							3,124.0	3,124.0	114.0			963.0
STA. 139+40.00 LT							58.4									
SHERIDAN ROAD																
STA. 700+15.00 TO STA. 706+65.00	1,647.0	38.9						0.24		1,575.0				408.0		
STA. 706+65.00 TO STA. 707+50.00								0.03	23.0							
SUBTOTAL	37,967.0	897.1	1,228.0	29,650.0	13.0	206.0	166.3	0.36	46.0	1,575.0	28,275.0	28,275.0	1,458.0	408.0	511.0	7,483.0
TOTAL	37,967	898	1,228	29,650	13	206	167	0.4	46	1,575	28,275	28,275	1,458	408	511	7,483

CONVERSION RATES
 ASPHALT: 112 LB/SQ YD IN
 AGGREGATE = 2.05 TON/CU YD
 0.004 TONS = GALLON
 LIME = 47.25 LBS/SY/12" THICKNESS

MODIFIED URETHANE PAVEMENT MARKING SCHEDULE	PAVEMENT MARKING - LINE 4"	GROOVING FOR RECESSED PAVEMENT MARKINGS 5"	PAVEMENT MARKING - LINE 12"	GROOVING FOR RECESSED PAVEMENT MARKINGS 13"	PAVEMENT MARKING - LINE 24"	GROOVING FOR RECESSED PAVEMENT MARKINGS 25"	LETTERS AND SYMBOLS	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS, NUMBERS AND SYMBOLS	RAISED REFLECTIVE PAVEMENT MARKER	
LOCATION	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	SQ FT	TWO-WAY AMBER - 40'	ONE-WAY CRYSTAL - 80'
VETERANS DRIVE										
STA. 96+77.4 TO STA. 99+29.4 RT	84.0	84.0								
STA. 96+80.3 TO STA. 99+30.4 RT	500.0	500.0	42.5	42.5						3
STA. 97+58.0 TO STA. 99+29.4 LT	57.5	57.5								2
STA. 98+41.3 TO STA. 99+42.0 RT	184.5	184.5								
STA. 99+28.4 TO STA. 99+29.4 RT					51.0	51.0				
STA. 99+77.9 TO STA. 112+00.0 LT	1,257.0	1,257.0								
STA. 99+93.9 TO STA. 112+00.0 RT	1,257.0	1,257.0								
STA. 100+00.0 TO STA. 112+00.0 CL							62.4	62.4		
STA. 100+10.0 TO STA. 110+25.4 LT/RT					53.0	53.0				
STA. 100+10.0 TO STA. 103+25.5 LT	558.0	558.0								
STA. 100+10.0 TO STA. 112+00.0 LT	400.0	400.0							26	15
STA. 100+10.0 TO STA. 112+00.0 RT	400.0	400.0								15
STA. 100+10.0 TO STA. 102+52.0 LT			35.0	35.0						
STA. 100+25.4 TO STA. 112+00.0 RT	1,174.0	1,174.0							30	
STA. 104+75.5 TO STA. 112+00.0 LT	968.0	968.0								
STA. 104+75.5 TO STA. 112+00.0 RT	241.0	241.0								
STA. 112+00.0 TO STA. 124+00.0 LT	3,186.0	3,186.0							30	15
STA. 112+00.0 TO STA. 124+00.0 RT	3,186.0	3,186.0							30	15
STA. 112+00.0 TO STA. 124+00.0 CL							31.2	31.2		
STA. 124+00.0 TO STA. 136+00.0 LT	3,134.0	3,134.0							30	15
STA. 124+00.0 TO STA. 136+00.0 RT	3,134.0	3,134.0							30	15
STA. 124+00.0 TO STA. 136+00.0 CL							62.4	62.4		
STA. 135+50.0 TO STA. 136+00.0 LT/RT	200.0	200.0	38.0	38.0						
STA. 136+00.0 TO STA. 139+76.1 LT	376.5	376.5								
STA. 136+00.0 TO STA. 139+82.0 LT	131.0	131.0								
STA. 136+00.0 TO STA. 140+00.0 LT/RT	1,613.0	1,613.0	319.0	319.0			62.4	62.4	10	5
STA. 136+00.0 TO STA. 139+82.0 RT	131.0	131.0							10	5
STA. 136+00.0 TO STA. 139+85.5 RT	387.0	387.0								
STA. 139+84.5 TO STA. 139+82.0 RT			30.5	30.5						
BROADWAY ROAD										
STA. 81+81.3 TO STA. 82+01.3 RT					57.0	57.0				
STA. 83+06.0 TO STA. 83+06.0 LT/RT					35.5	35.5				
STA. 83+84.7 TO STA. 91+67.3 RT	773.0	773.0								
SHERIDAN ROAD										
STA. 700+15.0 TO STA. 707+50.0 CL	1,470.0	1,470.0								
STA. 700+15.0 TO STA. 707+50.0 LT	738.0	738.0								
STA. 700+15.0 TO STA. 704+10.0 RT	393.0	393.0								
STA. 704+10.0					11.5	11.5				
STA. 705+20.0					9.0	9.0				
STA. 706+09.3 TO STA. 707+50.0 RT	141.0	141.0								
SUBTOTAL	26,086.5	26,086.5	434.5	434.5	247.5	247.5	218.4	218.4	196	105
TOTAL	26,087	26,087	435	435	248	248	218	218	196	105

SIGNING SCHEDULE			SIGN PANEL - TYPE 1	WOOD SIGN SUPPORT	SIGN PANEL - TYPE 2
LOCATION	SIGN CODE	MESSAGE OR DESCRIPTION	SQ FT	FOOT	SQ FT
VETERANS DR					
103+50	RT R2-1	SPEED LIMIT 55	7.50	16	
104+00	LT W3-3	SIGNAL AHEAD	6.25	16	
	W17-100	BROADWAY RD	1.90		
134+00	RT W2-4	T INTERSECTION	6.25	16	
	RT W17/100	SHERIDAN RD	1.90		
136+00	LT R2-1	SPEED LIMIT 55	7.50	16	
136+55	RT W3-1	STOP AHEAD	6.25	16	
139+85	RT R1-1	STOP	8.75	16	
	R1-3P	ALL WAY	0.75		
CALIFORNIA RD					
114+50 LT	OM4-1	REFLECTIVE SIGNING	2.25	17	
114+50 LT	OM4-1	REFLECTIVE SIGNING	2.25	17	
114+50 LT	R11-100	ROAD ENDS		34	10.00
50' SOUTH OF MARION RD.	R11-2	ROAD CLOSED		17	10.00
75' SOUTH OF SHERIDAN RD.	W14-1	DEAD END	6.25	17	
SHERIDAN RD					
702+00	RT W3-1	STOP AHEAD	6.25	16	
704+10	RT R1-1	STOP	8.75	16	
	R1-3P	ALL WAY	0.75		
705+00	LT W1-7	DOUBLE ARROW	8.00	32	
705+20	LT R1-1	STOP	8.75	16	
	R1-3P	ALL WAY	0.75		
707+00	LT W3-1	STOP AHEAD	6.25	16	
TOTAL			98.00	294	20.00