

STATION	STREET LIGHTS						
	OFFSET		LIGHT UNIT, COMPLETE	LIGHT UNIT, COMPLETE	250 W. LUM. ON 30' H. POLE*		
	FT LT	FT RT				EACH	EACH
HAMPSHIRE STREET - 3RD TO 4TH							
STA 30+56		25.0	1				
STA 30+90	25.4		1				
STA 31+26		25.2	1				
STA 31+62	25.3		1				
STA 31+94		25.0	1				
STA 32+37	25.3		1				
STA 32+61		24.9	1				
STA 33+12	25.5		1				
STA 33+30		24.8	1				
STA 33+87	25.5		1				
STA 33+99		24.7	1				
STA 34+26	24.7				1		
4TH STREET - HAMPSHIRE TO VERMONT							
STA 40+41		26.2			1		
STA 40+65	25.2		1				
STA 41+11		25.1	1				
STA 41+35	25.0		1				
STA 41+85		25.1	1				
STA 42+05	25.1		1				
STA 42+60		25.2	1				
STA 42+79	25.0		1				
STA 43+35		25.0	1				
STA 43+47	24.9		1				
STA 44+06		25.0	1				
STA 44+15	24.9		1				
STA 44+33	24.9				1		
VERMONT STREET - 3RD TO 4TH							
STA 23+13		23.5	1				
STA 23+83		23.5	1				
4TH STREET - VERMONT TO BROADWAY							
STA 45+3		26.3			1		
VERMONT STREET - 4TH TO 5TH							
STA 25+23	23.1		1				
STA 25+23		23.5	1				
STA 25+93	23.1		1				
STA 26+08		23.1	1				
STA 26+63	23.1		1				
STA 26+98		23.1	1				
STA 27+33	23.1		1				
STA 27+70		23.1	1				
STA 28+03	23.1		1				
STA 28+40		23.1	1				
STA 28+73	23.1		1				
5TH STREET - HAMPSHIRE TO BROADWAY							
STA 49+63	24.2		1				
STA 50+48		48.4	1				
STA 50+82	37.0		1				
STA 51+16		48.3	1				
STA 51+55	37.1		1				
STA 51+84		48.1	1				
STA 52+28	37.1		1				
STA 52+57		47.8	1				
STA 53+00	37.2		1				
STA 53+30		47.7	1				
TOTAL					34	11	4

*POLE THAT 250 W. LUMINAIR IS MOUNTED ON VARIES (SEE ELECTRIC SCHEDULES OF QUANTITIES)

STATION OF 7'x5' TREE WELL	TREES							
	OFFSET		RED MAPLE	SHADEMASTER HONEYLOCUST	PAPERBARK MAPLE	CORALBURST CRABAPPLE	CHANTICLEER CALLERY PEAR	JAPANESE TREE LILAC
	FT LT	FT RT						
HAMPSHIRE STREET - 3RD TO 4TH								
30+63.1	26.4						1	
30+79.3		25.95		1				
31+48.9		25.85	1					
31+71.6		25.83			1			
31+87.1	26.35		1					
32+13.6	26.41				1			
32+16.6		25.82			1			
32+38.9		25.84	1					
32+79.3		25.8		1				
33+37.1	26.41						1	
33+62.1	26.44				1			
33+67.8		25.68					1	
34+05.2	26.50							1
4TH STREET - HAMPSHIRE TO VERMONT								
40+64.0		26.09	1					
40+88.0		26.11			1			
41+58.7	25.97							1
41+82.0	26.01					1		
42+01.4		26.14		1				
43+01.6	25.92			1				
43+24.3	25.91				1			
43+55.9		26.14	1					
43+69.6	25.9		1					
43+92.3	25.87			1				
VERMONT STREET - 3RD TO 4TH								
23+35.8		24.50	1					
23+59.2		24.50			1			
24+02.5		24.50			1			
VERMONT STREET - 4TH TO 5TH								
25+46.5	24.08		1					
25+69.9	24.08				1			
26+16.5	24.08			1				
26+95.2	24.08		1					
27+61.1		24.08		1				
28+26.5	24.08							1
28+27.0		24.08			1			
28+49.9	24.08					1		
TOTAL			9	8	9	2	2	4

DOMESTIC WATER SERVICE BOX TO BE ADJUSTED			
LOCATION	OFFSET		EACH
	LT	RT	
HAMPSHIRE STREET			
STA. 31+52	24.08		1
STA. 31+87		27.4	1
STA. 32+01	24.57		1
STA. 32+09	23.99		1
STA. 33+86		24.68	1
STA. 33+87		24.61	1
FOURTH STREET			
STA. 43+71		25.82	1
STA. 43+73		24.97	1
VERMONT STREET			
STA. 27+2		21.78	1
TOTAL			9

WATER METER VAULT REMOVAL			
LOCATION	OFFSET		EACH
	LT	RT	
FOURTH STREET			
STA. 44+1	27.54		1
TOTAL			1

DOWNSPOUT TRENCH DRAINS			
STATION	OFFSET		LENGTH
	FT LT	FT RT	
HAMPSHIRE STREET			
STA 33+50		22	11
STA 33+89		22	11
TOTAL			22

REMOVE EXISTING CONCRETE FOUNDATION			
LOCATION	OFFSET		EACH
	LT	RT	
HAMPSHIRE STREET			
STA. 30+45		24.72	1
STA. 31+50	24.24		1
STA. 32+21		23.51	1
STA. 33+70		23.35	1
STA. 34+26	24.69		1
4TH STREET			
STA. 41+6	24.67		1
STA. 42+6		28.06	1
STA. 43+26	25.35		1
STA. 44+25		34.49	1
VERMONT STREET			
STA. 24+5		23.14	1
STA. 25+61		23.24	1
STA. 26+7		23.34	1
STA. 27+33	23.04		1
STA. 28+27		22.96	1
STA. 29+78	28.4		1
5TH STREET			
STA. 49+68	24.01		1
STA. 50+71		38.35	1
STA. 52+94		37.72	1
TOTAL			18

BOLLARDS			
LOCATION	OFFSET		EACH
	LT	RT	
VERMONT STREET			
STA. 26+97		225.26	1
STA. 26+99		223.56	1
TOTAL			2

TREE REMOVAL			
STATION	OFFSET		6 - 15
	FT LT	FT RT	
VERMONT STREET			
STA 27+61		24	11
TOTAL			11