



SHEET ITEM	STREET	PAY ITEM	MUTCD NO.	DISCRIPTION	UNIT	QUANTITY	STA	O.S.	LT/RT	NOTES	FACE
1	HAMPSHIRE	72400200 - REMOVE SIGN PANEL ASSEMBLY - TYPE B		STOP SIGN WITH ONE WAY SIGN	EA	1					N/A
2	HAMPSHIRE	72000100 - SIGN PANEL - TYPE 1	R1-1	30" X 30" STOP SIGN	SQ. FT.	6.25	30+42	25.7	LT		E
3	HAMPSHIRE	72000100 - SIGN PANEL - TYPE 1	R6-2	24"X30" ONE WAY SIGN	SQ. FT.	5	30+37	25	RT		W
4	HAMPSHIRE	72000100 - SIGN PANEL - TYPE 1	D3-1	STREET SIGN - HAMPSHIRE	SQ. FT.	3	30+45	25	RT	INSTALL ON TOP OF 1-WAY SIGN	N/S
5	HAMPSHIRE	72000100 - SIGN PANEL - TYPE 1	D3-1	STREET SIGN - NORTH 3RD	SQ. FT.	3	30+45	25	RT		E/W
6	HAMPSHIRE	72400710 - RELOCATE SIGN PANEL - TYPE 1		EMERGENCY SNOW ROUTE	SQ. FT.	9	33+36	24.7	RT	INSTALL ON NEW LIGHT POST	W
7	HAMPSHIRE	72000100 - SIGN PANEL - TYPE 1	R7-8	12"X18" RESTRICTED PARKING	SQ. FT.	3	34+10	24	RT		W
8	HAMPSHIRE	72000100 - SIGN PANEL - TYPE 1	R7-1101	12"X6" PLAQUE	SQ. FT.	0.5				#250 FINE	W
9	HAMPSHIRE	72400100-REMOVE SIGN PANEL ASSEMBLY - TYPE A		RESTRICTED PARKING	EA	1					N/A
10	4TH STREET	72000100 - SIGN PANEL - TYPE 1	R6-2	30"X36" ONE WAY SIGN	SQ. FT.	7.5	42+00	25	LT		E
11	4TH STREET	72400710 - RELOCATE SIGN PANEL - TYPE 1		EMERGENCY SNOW ROUTE	SQ. FT.	3	41+87	25	LT	INSTALL ON NEW LIGHT POST	S
12	4TH STREET	72400100-REMOVE SIGN PANEL ASSEMBLY - TYPE A		ONE WAY SIGN WITH SNOW EMG. RTE	EA	1					N/A
13	4TH STREET	72000100 - SIGN PANEL - TYPE 1	R6-2	30"X36" ONE WAY SIGN	SQ. FT.	7.5	42+15	25.1	RT		W
14	4TH STREET	72400710 - RELOCATE SIGN PANEL - TYPE 1		EMERGENCY SNOW ROUTE	SQ. FT.	3	41+92	25.1	LT	INSTALL ON NEW LIGHT POST	S
15	4TH STREET	72000100 - SIGN PANEL - TYPE 1	W11-2	36"X36" PEDESTRIAN	SQ. FT.	9	42+60	25.2	RT	INSTALL ON NEW LIGHT POST	S
16	4TH STREET	72000100 - SIGN PANEL - TYPE 1	W11-2	36" X 36" PEDESTRIAN	SQ. FT.	9	42+79	25	LT	INSTALL ON NEW LIGHT POST	S

