

STORM SEWER & PIPE CULVERT SCHEDULE (CONTINUED)																									
FROM (STRUCTURE NO.)	PIPE INVERT	TO (STRUCTURE NO.)	PIPE INVERT	PLAN SLOPE	STORM SEWERS															WATER MAIN QUALITY PIPE		TRENCH BACKFILL (CU YD)			
					CLASS A										CLASS A					TYPE 1	TYPE 2				
					TYPE 1					TYPE 2					TYPE 1		TYPE 2								
12" RCP (FOOT)	15" RCP (FOOT)	18" RCP (FOOT)	21" RCP (FOOT)	24" RCP (FOOT)	36" RCP (FOOT)	12" RCP (FOOT)	15" RCP (FOOT)	18" RCP (FOOT)	24" RCP (FOOT)	30" RCP (FOOT)	48" RCP (FOOT)	21" RCP (FOOT)	30"x19" RCP (EQRS 24") (FOOT)	45"x29" RCP (EQRS 36") (FOOT)	30"x19" RCP (EQRS 24") (FOOT)	38"x24" RCP (EQRS 30") (FOOT)	45"x29" RCP (EQRS 36") (FOOT)	12" (FOOT)	24" (FOOT)						
FAIRGROUNDS AVENUE (CONTINUED FROM PREVIOUS SHEET)																									
60	607.93	61	608.39	4.00%	10																0.8				
59	607.79	62	611.53	2.50%							148										39.1				
62	611.53	63	611.82	1.00%	28																4.1				
60	607.93	64	608.28	0.50%												66					32.7				
64	608.28	65	611.89	9.00%																	1.5				
64	608.28	66	609.08	1.50%							51										19.1				
66	609.08	67	612.09	5.50%																53	1.9				
66	609.08	68	611.02	1.50%																	16.0				
68	611.02	69	612.77	6.00%																	6.4				
68	611.02	70	612.31	3.50%																	9.2				
70	612.31	71	612.85	1.00%																	9.1				
71	612.85	72	613.30	1.50%	29																4.6				
71	612.85	73	613.41	0.50%																	20.9				
73	613.41	74	614.00	2.00%	28																5.3				
73	613.41	75	614.33	1.25%																	14.6				
75	614.33	76	615.41	1.25%																	14.6				
76	615.41	77	615.85	0.50%																	4.1				
77	615.55	126	615.80	1.00%																	3.0				
116	598.62	122	599.27	0.62%																	103.5				
122	604.17	121	605.40	9.21%																	1.9				
122	599.27	114	599.45	0.53%																	57.2				
114	605.50	113	606.67	4.00%																	8.4				
114	605.50	79	610.18	4.00%																	37.8				
79	610.18	80	610.78	2.00%																	6.6				
79	610.18	81	611.37	1.00%																	34.9				
81	611.37	82	611.66	1.00%	28																8.3				
81	611.37	84	614.89	2.50%																	12.7				
84	614.89	85	616.92	5.50%																	0.8				
84	614.89	88	615.36	1.00%																	7.5				
88	615.36	87	617.49	6.00%																	0.9				
88	615.36	89	616.17	1.80%	43																6.0				
90	596.35	EX 48" PIPE	596.62	1.82%																	0.0				
116	597.49	91	597.95	1.82%																	0.0				
116	602.00	93	603.00	2.57%																	26.1				
93	604.27	94	605.15	3.00%	28																5.2				
93	603.25	112	604.90	3.14%																	5.7				
112	604.90	118	604.98	0.70%																	0.5				
112	604.90	95	605.13	0.50%																	8.0				
95	605.13	115	606.37	5.00%																	4.5				
115	606.37	96	606.98	2.00%																	4.8				
115	606.37	97	611.40	3.75%																	25.9				
97	611.40	98	612.13	2.50%	28																4.4				
97	611.40	99	614.38	2.00%																	15.1				
99	614.38	100	617.04	4.00%	65																0.7				
99	614.38	101	614.90	1.00%																	8.4				
101	614.90	102	616.84	5.00%																	0.8				
103	611.88	104	612.05	0.30%																	0.5				
104	612.05	105	612.25	0.50%																	9.5				
105	612.25	106	612.56	0.50%																	3.0				
106	612.56	117	614.70	13.10%																	0.0				
105	612.25	107	612.87	2.00%																	3.9				
107	612.67	108	613.46	1.00%																	11.7				
111	612.77	120	612.98	0.50%																	0.8				
120	612.98	119	613.13	0.50%																	6.2				
119	613.13	110	613.22	0.50%																	0.8				
TOTALS					743	909	682	601	193	51	470	619	255	75	223	174	120	172	111	44	43	92	106	53	1,282.1

FILE NAME =	USER NAME = Horgan, Chris	DESIGNED -- BJB	REVISED --
00140-321	DRAWN -- BJB	CHECKED -- DLK	REVISED --
	PLOT SCALE = 1:2	DATE -- 4/23/12	REVISED --
	PLOT DATE = 4/20/2012		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DRAINAGE STRUCTURE SCHEDULE	
SCALE: NA	SHEET NO. 15 OF 117 SHEETS STA. NA TO STA. NA

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8801	05-00034-01-RP	JERSEY	117	15
CONTRACT NO. 97371				