

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Schedule of Quantities

Various Routes
OVD SIN STR REP & REPL 2006-9
Various Counties
Sheet 5 of 89
Contract Number 44904

PAY ITEM	UNIT	Y002 - 1C 100% STATE TOTAL QUANTITY	DISTRICT 1	DISTRICT 2	DISTRICT 3	DISTRICT 4	DISTRICT 5	DISTRICT 7
REPLACE OVERHEAD SIGN WALKWAY	FOOT	36.00		20.00			16.00	
REMOVE & REINSTALL WALKWAY	FOOT	417.00		29.50	220.00		150.50	17.00
REMOVE & RE-ERECT OVERHEAD SIGN END SUPPORT	EACH	2.00				2.00		
OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	475.00	245.00	162.00		68.00		
REPLACE/TIGHTEN CLIP PER SIGN	EACH	5.00		4.00		1.00		
REMOVE & REINSTALL SIGN PANEL	SQ FT	3,824.50		700.00	1,652.00		1,169.75	302.75
REPLACE U-BOLT	EACH	16.00		4.00		12.00		
FURNISH & INSTALL SADDLE SHIM BLOCK	EACH	20.00	12.00	8.00				
REPAIR CONCRETE FOUNDATION FOR OVERHEAD SIGN STRUCTURE	EACH	4.00	1.00			3.00		
OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	47.00	12.00	4.00	20.00	7.00		4.00
FURNISH & INSTALL INTERNAL TRUSS CLAMP	EACH	1.00				1.00		
FURNISH & INSTALL INTERNAL TRUSS DAMPER	EACH	11.00	3.00	2.00		5.00		1.00
FURNISH & INSTALL SAFETY CHAIN	EACH	42.00	4.00	8.00	8.00	10.00	8.00	4.00
TIGHTEN CANTILEVER CONNECTION	EACH	4.00				4.00		
FURNISH & INSTALL WALKWAY TIE DOWN BOLT	EACH	1.00				1.00		
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	49.00		4.00		33.00		12.00
REPLACE HANDRAIL SUPPORT	EACH	2.00		2.00				