

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Various Routes
OVD SIN STR REP & REPL 2006-9
Various Counties
Sheet 50 of 89
Contract Number 44904

District 5
Schedule of Locations for Overhead Sign Structure Repair and Replacement

Location No.:	5-01	State I.D. No.:	5S0101072L182.12				
County:	Champaign	Route:	I - 72	M.P.:	182.12	Direction:	WB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE I A	FOOT	76.00					
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	12.70					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	379.00					
REMOVE & REINSTALL WALKWAY	FOOT	61.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	1.00					
Existing design plans are not available for this structure.							

Location No.:	5-02	State I.D. No.:	5S0101057R239.96				
County:	Champaign	Route:	I - 57	M.P.:	239.96	Direction:	NB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
OVERHEAD SIGN STRUCTURE SPAN, TYPE I A	FOOT	60.33					
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	12.00					
REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	2.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	276.25					
REMOVE & REINSTALL WALKWAY	FOOT	36.50					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00					
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	1.00					

Location No.:	5-03	State I.D. No.:	5S0101074R178.7				
County:	Champaign	Route:	I - 74	M.P.:	178.7	Direction:	EB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
OVERHEAD SIGN STRUCTURE-SPAN TYPE I A	FOOT	78.00					
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	182.00					
OVERHEAD SIGN STRUCTURE WALKWAY (SPECIAL)	FOOT	20.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					

Location No.:	5-04	State I.D. No.:	5S0921074R214.0				
County:	Vermilion	Route:	I - 74	M.P.:	214.00	Direction:	EB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
OVERHEAD SIGN STRUCTURE-SPAN TYPE I A	FOOT	86.00					
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	20.40					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	332.50					
REMOVE & REINSTALL WALKWAY	FOOT	53.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
CONCRETE REMOVAL (SPECIAL)	SQ YD	108.40					
IMPACT ATTENUATORS, RELOCATE (NON-DIRECTIVE) TL 3	EACH	2.00					
REPLACE OVERHEAD SIGN WALKWAY	FOOT	16.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	1.00					
This locations will require additional traffic control due to being located on a collector distributor route.							