

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

Various Routes  
OVD SIN STR REP & REPL 2006-9  
Various Counties  
Sheet 67 of 89  
Contract Number 44904

District 7  
Schedule of Locations for Truss Repair & Replacement

Location No.:	7-01	State I.D. No.:	7S051U050L014.8		
County:	Lawrence	Route:	U. S. 50	M.P.:	14.8
				Direction:	WB
Description of Work		Unit	Quantity		
OVERHEAD SIGN SUPPORT GROUT REPAIR		EACH	4.00		
REPAIR HANDRAIL LOCKING PIN CONNECTION		EACH	12.00		
FURNISH & INSTALL SAFETY CHAIN		EACH	2.00		
FURNISH & INSTALL INTERNAL TRUSS DAMPER		EACH	1.00		

Location No.:	7-02	State I.D. No.:	7C025I057R166.1		
County:	Effingham	Route:	I-57	M.P.:	166.1
				Direction:	NB
Description of Work		Unit	Quantity		
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER		EACH	1.00		
REMOVE CONCRETE FOUNDATION-OVERHEAD		EACH	1.00		
OVERHEAD SIGN STRUCTURE CANTILEVER 2CA3-0X5-6		FOOT	30.00		
DRILLED SHAFT CONCRETE FOUNDATION		CU YD	7.20		
REMOVE & REINSTALL SIGN PANEL		SQ FT	74.75		
REMOVE & REINSTALL WALKWAY		FOOT	17.00		
FURNISH & INSTALL SAFETY CHAIN		EACH	2.00		
RELOCATE ELECTRIC SERVICE		EACH	1.00		
DISCONNECT/RECONNECT ELECTRIC SERVICE		EACH	1.00		
UNIT DUCT, 2#10 XLP, 1#10 XLP GROUND 3/4" POLYETHYLENE		FOOT	150.00		
This overhead sign structure is being completely replaced.					

Location No.:	7-03	State I.D. No.:	7C026U051L011.0		
County:	Fayette	Route:	U.S. 51	M.P.:	11
				Direction:	SB
Description of Work		Unit	Quantity		
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER		EACH	1.00		
REMOVE CONCRETE FOUNDATION-OVERHEAD		EACH	1.00		
STEEL MAST ARM ASSEMBLY & POLE, 28 FOOT		EACH	1.00		
CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER		FOOT	10.00		
REMOVE & REINSTALL SIGN PANEL		SQ FT	93.00		
MEDIAM SURFACE REMOVAL		SQ FT	128.00		
CONCRETE MEDIAN SURFACE, 4 INCH		SQ FT	128.00		
REMOVE ELECTRIC SERVICE		EACH	1.00		
This overhead sign structure is being replaced with a steel mast arm and pole assembly.					

Location No.:	7-04	State I.D. No.:	7C026U051R010.9		
County:	Fayette	Route:	U.S. 51	M.P.:	10.9
				Direction:	NB
Description of Work		Unit	Quantity		
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER		EACH	1.00		
REMOVE CONCRETE FOUNDATION-OVERHEAD		EACH	1.00		
REMOVE ELECTRIC SERVICE		EACH	2.00		
REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE		EACH	1.00		
REMOVE EXISTING SIGN		SQ FT	82.00		
This overhead sign structure is being completely removed.					

Location No.:	7-05	State I.D. No.:	7C026U051R011.0		
County:	Fayette	Route:	U.S. 51	M.P.:	11
				Direction:	NB
Description of Work		Unit	Quantity		
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER		EACH	1.00		
REMOVE CONCRETE FOUNDATION-OVERHEAD		EACH	1.00		
STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 30 FT.		EACH	1.00		
CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER		FOOT	13.50		
UNIT DUCT, 2#10 XLP, 1#10 XLP GROUND 3/4" POLYETHYLENE		FOOT	400.00		
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C		FOOT	686.00		
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C		FOOT	186.00		
TRAFFIC SIGNAL BACKPLATE, LOUVERED		EACH	4.00		
REMOVE ELECTRIC CABLE FROM CONDUIT		FOOT	647.00		
REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT		EACH	1.00		
SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE,					
3-SECTION, BRACKET MOUNTED		EACH	1.00		
SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE,					
3-SECTION, MAST ARM MOUNTED		EACH	2.00		
SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE,					
5-SECTION, BRACKET MOUNTED		EACH	1.00		
REMOVE & REINSTALL SIGN PANEL		SQ FT	135.00		
CONDUIT IN TRENCH, 2 1/2 INCH DIAMETER PVC		FOOT	25.00		
LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT,					
PHOTOCELL CONTROL, 250 WATT		EACH	1.00		